

ILLEGIB

Approved For Release 2002/11/15 : CIA-RDP78T05439A000100250031-0

Next 8 Page(s) In Document Exempt

Approved For Release 2002/11/15 : CIA-RDP78T05439A000100250031-0

TOP SECRET [REDACTED]

RADIO STATIONS
WITHIN A
50-NAUTICAL-MILE RADIUS OF MOSCOW

PIC/JR-8/59
JUNE 1959

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

25X1C

PREFACE

This joint photographic intelligence report has been prepared by the Army, Navy, and Central Intelligence Agency, under CIA chairmanship.

[REDACTED] Microwave communication facilities are covered separately in PIC/JR-9/59.

Information based on an analysis of aerial and ground photography has been supplemented by data from numerous collateral reports. A helpful analysis of these reports through 1958 was prepared by [REDACTED]

25X1A

Stations described in detail in this report are named after the nearest town. Numbers have been assigned to all stations for convenient map and table reference. Radio stations with at least 50 stick masts are called antenna farms. Distances from Moscow are measured from the Kremlin. Both geographic and UTM coordinates are given for locations of installations; the UTM coordinates are from AMS Map Series NS01, scale 1:250,000.

- 3 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

TABLE OF CONTENTS

	Page
General	7
No. 6. Bratovshchina Radio Station	9
No. 8. Noginsk Radio Station	14
No. 9. Noginsk Radio Station	20
No. 10. Shchelkovo Radio Station	25
No. 14. Radio Station Near Mytishchi	31
No. 15. Belyaninovo Radio Station	35
No. 30. Kupavna Antenna Farm	42
No. 31. Elektrostal Radio Station	46
No. 35. Bykovo Radio Station	50
No. 37. Biryulevo Antenna Farm	54
No. 40. Domodedovo Antenna Farm	57
No. 46. Butovo Antenna Farm	62
Nos. 49, 50, 53, and 54. Communications Complex Near Desna	67
No. 57. Kommunarka Antenna Farm	89
No. 58. Teplyy Stan Antenna Farm	92
No. 59. Vorontsovo Antenna Farm	97
No. 62. Tolstopaltsevo Antenna Farm	103
No. 67. Chernovo Radio Station	107
No. 89. Moscow Radio Station	112
No. 94. Moscow Television Station	119
No. 98. Moscow Radio Station	124
No. 103. Moscow Radio Station	126
No. 104. Moscow Radio Station	128
No. 107. Oktyabr'skiy Antenna Farm	130
No. 108. Moscow Radio Station	138
Tabulation of Radio Stations Within A 50-Nautical-Mile Radius of Moscow	142-181
Ground Photos of Ten Radio Stations	182

- 5 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

GENERAL

This report is a comprehensive analysis, based on aerial and ground photography and collateral sources, of 105 radio stations, including 18 antenna farms with over 50 masts each; one television station; and three Krug sites within a 50-nautical-mile (nm) radius of Moscow. Excluded are microwave facilities, air navigation facilities other than the Krug sites which may be associated with air navigation, and surface-to-air communication facilities of the kind normally found at airfields.

Of the 109 installations, 44 have been identified from photography. Aerial photography [REDACTED] covers about half of the area within a 50-nm radius of Moscow, but less than one fourth of this coverage is usable (i.e., less than one eighth of the total area), the remainder being cloud covered. Seventeen installations have been identified on this photography. World War II aerial photography covers the reported locations of 108 of the 109 installations included in this report. However, only 22 stations can be identified on this [REDACTED] photography. Ground photography [REDACTED] is available for 35 of the 109 listed installations. A comparison of the 22 stations identifiable on World War II aerial photography with later coverage [REDACTED] aerial photography and 1954-1958 ground photography reveals that nearly all have been expanded since [REDACTED] in the number of structures or antennas.

- 7 -

TOP SECRET [REDACTED]

TOP SECRET

PIC/JR-8/59

A detailed photographic analysis has been prepared on 28 installations, using aerial photography for 25 and ground photography for 3. All data available on the remaining 81 installations has been tabulated in a table beginning on page 142 of this report. This data includes the type, location, and description of each installation. This report also includes two maps, one showing the location of the installations within a 50-nm radius of the city of Moscow (enclosed at the end of this report), and the other showing the location of the installations within the city proper (see page 111). Ground photography on 10 of the 81 tabulated stations appears on pages 182 thru 186.

- 8 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 2. LINE DRAWING OF BRATOVSHCHINA RADIO STATION

- 10 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 6

BRATOVSHCHINA RADIO STATION

I. GENERAL

Bratovshchina Radio Station is located 22 nautical miles north-northeast of Moscow on the east side of the Moscow/Zagorsk highway between the 43 and 45 kilometer markers (Figure 1). The station, which is served by an all-weather road, covers approximately 720 acres.




FIG. 1. LOCATION MAP

Aerial photography shows the station to include two areas. One area (A in Figure 2), enclosed by a fence, contains a large T-shaped control building, a possible cooling tower, barracks, and eight self-supporting lattice towers. The other area (B in Figure 2), located immediately south of Area A, was under construction in 1942. Ground photography of 1950-57 indicates that Area B had been completed and that both areas had undergone considerable expansion in both structures and antennas.

- 9 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

II. STRUCTURES

Ground photography of 1950-57 shows several buildings not on photography, including one reported to measure 150 by 70 feet and three large two-story, hip-roofed possible barracks (Figure 3). The




FIG. 3. THREE LARGE TWO-STORY POSSIBLE BARRACKS AT BRATOVSHCHINA RADIO STATION (1957)

following is a tabulation of the significant structures in the station area appearing on photography (item numbers are keyed to Figure 2).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
Area A				
1	Control building	3	Flat	-
1a	Base	3	-	180 x 60
1b	Wing	3	-	160 x 55
2	Possible cooling tower	-	-	35 x 35 x 40
3	7 barracks	1	Gable	160 x 55
4	Probable guardhouse	1	Gable	145 x 40
5	Support-type building	1	Gable	145 x 40
6	Support-type building	1	Gable	125 x 90
Area B				
1	Possible control building U/C	-	-	125 x 90

- 11 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

III. ANTENNAS

Aerial photography [] shows eight self-supporting lattice towers within Area A. Three of these towers (Figure 2, items a-c) are on the northwest side of Area A. A perpendicular to a line projected between these towers has an azimuth orientation of [] degrees. The other five towers (Figure 2, items d-h) are on the northeast side of the area. A perpendicular to a line projected between towers d-g has an azimuth orientation of 70/250 degrees and between towers g and h an azimuth orientation of [] degrees. Each tower measures approximately 220 feet high, and the towers are approximately 400 feet apart. Ground photography of 1950-1958 (Figure 4) shows numerous steel self-supporting lattice towers supporting curtain antenna arrays; numerous stick masts, some of which appear to form rhombic patterns; and numerous VHF yagi-type antennas mounted on poles.



FIG. 4. SIX SELF-SUPPORTING LATTICE TOWERS AT BRATOVSHCHINA RADIO STATION (1957)

Collateral reports from 1950 to 1958 indicate that this station includes two groups of tall towers; the northernmost group is reported to contain 18 towers arranged in a U shape with the closed end roughly facing the Moscow/Zagorsk highway. The southernmost group is reported to contain approximately 25 towers 300 feet high and 80 feet apart and arranged in a

- 12 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

circle or arc. Both groups support curtain arrays. There are also numerous stick masts in the area which are reported to be 80 to 100 feet high and possibly arranged in rhombic patterns.

PHOTO DATA:

Aerial Photography

Ground Photography

MAP DATA:

COLLATERAL REPORTS:

25X1C

COORDINATES: 56°05'N/37°37'E

- 13 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 8

NOGINSK RADIO STATION

1. GENERAL

Noginsk Radio Station (No. 8) is located 27 nautical miles (nm) east of Moscow, 3 nm southwest of Noginsk, and just north of the Moscow/Noginsk highway (Figure 5). This radio station, which is a point-to-point




FIG. 5. LOCATION MAP

transmitter station (Figure 6), is partially enclosed by a wire fence and covers approximately 85 acres (2,900 x 1,250 feet). Aerial photography [] and ground photography of 1948 show this station to include a transmitter building, a cooling pond, two support-type buildings, a guardhouse, 12 antenna towers arranged in 6 pairs, and 5 double-end-pole rhombic antennas.

- 14 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 6. NOGINSK RADIO STATION (NO. 8)

- 15 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

II. STRUCTURES

The following is a tabulation of all structures within the station area (item numbers are keyed to Figure 7).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Transmitter building	3	Complex	140 x 100
2	Support-type building	1	Hip	100 x 70
3	Support-type building	1	Gable	45 x 25
4	Guardhouse	1	Shed	
5	Cooling pond	-	-	55 dia.




FIG. 7. LINE DRAWING OF NOGINSK RADIO STATION (NO. 8)

- 16 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 8. NOGINSK RADIO STATION (NO. 8) (1948)
 Two-stacked Parasitic Arrays mounted on self-supporting towers.
 Four-stacked Parasitic Arrays mounted on self-supporting lattice towers, control building in background.

III. ANTENNAS

The antenna field appearing on [] photography contains 12 self-supporting steel lattice towers arranged in six pairs (Figure 7, items F-K). The antennas supported by these towers are high-frequency directional horizontal dipoles. Each antenna unit consists of a driver element and a parallel reflector element. These antenna units are stacked on the towers (Figure 8). A feed line extends from the control building and splits near each tower base to center-feed the driver elements.

The item letters in the following table are keyed to the tower pairs on Figure 7.

- 17 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item Letter	Tower Height (feet)	No. of Stacked Units	Unit Heights Above Ground (feet)	Driver Elements Dimensions (feet) Length Diameter	Reflector Element Dimensions (feet) Length Diameter
F	100	2	50, 100	35	40
G	100	2	50, 100	35	40
H	140	4	35, 70, 105, 140	18	20
I	100	4	25, 50, 70, 100	15	20
J	100	2	50, 100	35	40
K	100	4	25, 50, 75, 100	15	20

* Approximate

The dimensions in the above table are taken from NIS 26, Supplement III, Telecommunications, May 1949, page 31 (S).

The distance between the driver elements and reflector elements is as follows: items F, G, and J, 20 feet; and items H, I, and K, 10 feet.

A possible ground screen is attached to the towers in items G and H. There are two possible wave traps connected to the transmitter building.

The antenna field also contains five double-end-pole rhombics for point-to-point communications. Each rhombic in the double rhombic patterns has a dissipation line. The item letters in the following table are keyed to Figure 7.

Item Letter	Mast Height (feet)	Major Axis (feet)	Minor Axis (feet)	Side Length (feet)	Distance Between End Poles (feet)	Dissipation Line Length (feet)
A	70	610	320	50	480	480
B	70	610	270	50	480	480
C	70	610	340	50	480	480
D	70	750	420	50	500	500
E	70	750	420	50	500	500

IV. OVERHEAD POWER AND/OR COMMUNICATIONS LINES

A power line with its line of lead in an east/west direction is located 500 feet south of the site. No connection between this line and the area can be determined.

- 18 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

MAP DATA: ATMP

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°50'N/38°22'E

25X1D

- 19 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 9

NOGINSK RADIO STATION

I. GENERAL

Noginsk Radio Station (No. 9) is located 27 nautical miles (nm) east of Moscow, 3 nm southwest of Noginsk, and just north of the Moscow/Noginsk highway (Figure 9). This station, which is a local broadcasting station located 5,000 feet west of Noginsk Radio Station (No. 8), is enclosed by a fence and covers approximately 68 acres (2,100 by 1,400 feet). Aerial photography [] reveals the station to include an operations area with a control building and adjacent cooling pond, a guardhouse, two guyed steel masts, and a support area (Figure 10).




FIG. 9. LOCATION MAP

- 20 -

TOP SECRET

TOP SECRET

PIC/JR-8/59



FIG. 10. NOGINSK RADIO STATION (NO. 9)

- 21 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

II. STRUCTURES

The following is a tabulation of the structures within the operations and support areas as [] (item numbers are keyed to Figure 11).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
Operations Area				
1	Control building	2	Gable & Shed	145 x 90
2	Possible administration bldg.	1	Gable	35 x 15
3	Guardhouse	1	Shed	10 x 10
4	Support-type building	1	Gable	130 x 35
5	Cooling pond	-	-	60 dia.
Support Area				
1	Administrative & barracks bldg.	3	Complex	-
1a	Base	3	-	180 x 70
1b	Wing	3	-	110 x 65
1c	Wing	3	-	110 x 50
2	Unidentified	1	Shed	15 x 15
3	Unidentified	1	-	40 x 25
4	Warehouse-type building	1	-	75 x 20
5	Barracks-type building	2	Gable	150 x 70
6	Warehouse-type building	1	-	60 x 25
7	Warehouse-type building	1	Gable	70 x 25
8	Warehouse-type building	1	Gable	40 x 20
9	Unidentified	1	Shed	15 x 15
10	Warehouse-type building	1	Gable	160 x 40
11	Unidentified	2	Hip	60 x 35

III. ANTENNA

The two steel masts are approximately 330 feet high and 860 feet apart. Each mast is supported by guy wires fastened to four pairs of

- 22 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

anchor bases. Each pair consists of two anchors placed at right angles to and 300 and 500 feet, respectively, from the base of each mast.

IV. OVERHEAD POWER AND/OR COMMUNICATION LINES

A power line which extends in an east/west direction is located




FIG. 11. LINE DRAWING OF NOGINSK RADIO STATION (NO. 9)

- 23 -

TOP SECRET

TOP SECRET [REDACTED]

PIC/JR-8/59

500 feet south of the station. No connection between this line and the station can be determined.

MAP DATA: ATMP [REDACTED]

25X1D

COLLATERAL REPORTS:

COORDINATES: 55°50'N/38°21'E

25X1D

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 10

SHCHELKOVO RADIO STATION

1. GENERAL

Shchelkovo Radio Station is located 17.5 nautical miles (nm) northeast of Moscow, 3 nm southeast of Shchelkovo, and 625 feet east of the Chalkalovskaya Railroad Station (Figure 12). It is served by an all-weather road, is enclosed by a fence, and covers approximately 40 acres (1,400 by 1,200 feet). Aerial photography [REDACTED] shows the station to consist of an operations area with a transmitter building and two short guyed masts, and support area. Also visible are three bases for lattice masts, four excavations for stick masts, and numerous guy-wire anchors (Figure 13). These bases and guy-wire anchors indicate the prior existence of two tall guyed




FIG. 12. LOCATION MAP

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59



FIG. 13. SHCHELKOVO RADIO STATION

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

lattice masts, possible vertical radiators, and of a mast similar to the two guyed masts present [REDACTED]. The four excavations indicate the prior existence of a rhombic antenna. This station is reported to have begun operations in November 1929 as the broadcasting station of the All-Union Council of Trade Unions. By 1952, the function of the station may have been changed, as suggested by the removal of the two tall masts.



FIG. 14. TRANSMITTER BUILDING AT SHCHELKOVO RADIO STATION

11. STRUCTURES

The transmitter building, the only structure within the fenced operations area, is a complex-type building with over-all dimensions of approximately 120 by 80 feet (Figure 14). The following is a tabulation of the structures within the support area [REDACTED] (item numbers are keyed to Figure 15).

TOP SECRET [REDACTED]

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Barracks	2 or 3	Hip	110 x 45
2	Barracks	2 or 3	Hip	110 x 45
3	Barracks	2 or 3	Hip	110 x 45
4	Unidentified	-	-	45 x 30
5	Unidentified	-	-	35 x 25
6	Unidentified	1	-	45 x 30
7	Unidentified	1	-	30 x 25
8	Warehouse-type building	1	Gable	70 x 35
9	Warehouse-type building	1	Gable	50 x 30
10	Unidentified	1	-	25 x 15
11	Unidentified	1	-	15 x 15
12	Guardhouse	1	-	15 x 15

III. ANTENNAS

The two short guyed masts appearing on aerial photography are approximately 65 feet high and approximately 500 feet apart. The two tall guyed lattice masts, which had been removed, were spaced 825 feet apart and were supported by four pairs of guy-wire anchors. Each pair consisted of two anchors placed at right angles to and 165 and 330 feet, respectively, from the base of each mast. The four excavations and the guy-wire anchors which formed the rhombic antenna indicate that this antenna had a side length of 350 feet, a minor axis of 295 feet, a major axis of 630 feet, and an azimuth orientation of degrees (Figure 15).

Collateral information from 1948 through 1952 reports one steel tower 240-300 feet high and several smaller masts 60 feet high.

IV. POWER AND/OR COMMUNICATION LINES

Two power lines with their line-of-lead in a north-south direction are

- 28 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 15. LINE DRAWING OF SHELKOVO RADIO STATION

- 29 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

located along the east side of the station. A single pole located in the middle of the eastern fence line indicates that the area is probably supplied with power from this source.

25X1D

25X1C

MAP DATA:

ATMP

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°54'N/38°04'E

25X1D

- 30 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 14

RADIO STATION NEAR MYTISHCHI

A radio station is reported to be located on the grounds of the Moscow Military Communications Institute just northwest of the town of Mytishchi (Figure 16). Mytishchi is 11.5 nautical miles northeast of Moscow. This station is reported to be located in the north part of the institute grounds and aerial photography reveals six various-sized buildings surrounded by a wall in this area (Figures 17 and 18). There are no masts or antennas visible on the aerial photography. Ground photography of 1957-1958 reveals numerous guyed stick masts located on the northwest side of the




FIG. 16. LOCATION MAP

- 31 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 17. MOSCOW MILITARY COMMUNICATIONS INSTITUTE

TOP SECRET

TOP SECRET

PIC/JR-8/59

grounds. Although no antenna pattern can be identified on the ground photography the area is reported to contain 21 stick masts each 50-60 feet high arranged in a 5-4-5-4-3 pattern oriented NW/SE. Also visible are several microwave parabolas mounted on steel masts, two Knife Rest radars, a parabola-shaped probable radar, and a self-supporting lattice tower with platforms and a large dish-shaped antenna mounted on one side (Fig 19).

The institute has been reported to be the most important Soviet Army Communications Research Institute and to conduct research on radar, telephone, and other equipment. The institute area is both road and rail-served and reportedly contains 60 administrative and storage-type buildings.




FIG. 18. LINE DRAWING OF MOSCOW MILITARY COMMUNICATIONS INSTITUTE

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 19. MOSCOW MILITARY COMMUNICATIONS INSTITUTE Sixteen stick masts can be seen (1956)

25X1D

25X1C

MAP DATA:
ATMP

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°56'N/37°44'E

25X1D

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 15

BELYANINOVO RADIO STATION

Belyaninovo Radio Station is located 12 nautical miles (nm) north of Moscow and one nm southeast of the village of Belyaninovo (Figures 20 and 21). Aerial photography shows this station to be served by a gravel road and to be at least partially secured by a board fence. The station consists of a small radio facility, reported in 1952-53 to contain from two to four stick masts with horizontal dipoles (Figure 23, item A), and




FIG. 25. LOCATION MAP

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 21. BELYANINOVO RADIO STATION

another radio facility which contains probable rhombic-type antennas (Figure 23, items B-E), as evidenced by forest clearings. Ground photography of 1956 shows that this new radio facility had been expanded since [] to include a cleared area to the south which contains at least 25 stick masts (Figure 23, item F). The estimated alignment of a power

- 36 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 22. BELYANINOVO RADIO STATION

- 37 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 23. LINE DRAWING OF BELYANINOVO RADIO STATION

- 38 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

transmission line, also appearing on 1956 ground photography, is shown on Figure 21. No connection between the power line and the radio station can be determined. A collateral report dated 1946-47 accurately describes most of the structures as they existed [] and certain additions not under construction at the time of the [] photographs.

II. STRUCTURES

The following is a tabulation of the structures within the station area (item numbers are keyed to Figure 23).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Possible control building	3	-	160 x 50
2	Possible control building	3	-	160 x 50
3	Support building	2	-	70 x 40
4	Support building	1	-	60 x 35
5	Support building	1	Hip	70 x 40
6	Possible apartment building	U/C	-	180 x 45
7	Possible apartment building	2	Gable	180 x 45
8	Possible apartment building	2	Gable	180 x 45
9	Support building	1	Shed	30 x 20
10	Support building	1	Shed	30 x 20
11	Support building	1	Gable	45 x 35
12	Support building	1	Gable	40 x 20
13	Support building	1	Gable	40 x 20
14	Support building	1	Hip	100 x 45
15	Possible apartment building	1	Gable	160 x 45
16	Possible apartment building	1	Gable	160 x 45
17	Support building	1	Hip	45 x 35
18	Barracks-type building	1	Gable	120 x 45
19	Barracks-type building	1	Gable	100 x 45
20	Support building	1	Gable	40 x 20

- 39 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
21	Barracks-type building	2	Hip	120 x 45
22	Barracks-type building	2	Hip	110 x 40
23	Barracks-type building	2	Hip	110 x 45
24	Administrative-type building (main)	1	Gable	140 x 40
25	Support building (L-shaped) (wing)	1	-	40 x 40
26	Support building (L-shaped) (main)	1	-	70 x 40
27	Support building (L-shaped) (wing)	1	Gable	40 x 20
28	Standpipe	-	-	20 dia. poss 65 high
29	Possible pumphouse	1	Gable	30 x 20
30	Possible control building (L-shaped) (main)	3	Hip	90 x 40
31	Support building (L-shaped) (wing)	2	Gable	70 x 20
32	Support building	1	Gable	60 x 30
				60 x 25

III. ANTENNAS

Aerial photography [] reveals four clearings in the woods which are located near the possible control buildings. The shape and location of these clearings indicate the existence of probable rhombic antennas. Other antennas include at least 25 stick masts identified on 1956 ground photography. The following is a list of these antennas (letter designations are keyed to Figure 23).

Item Letter	Configuration	Clearing Major Axis	Dimensions (feet) Minor Axis	Approx. Azimuth Orientation (degrees)
B	Prob. rhombic	800	300	90/270
C	Prob. rhombic	800	300	70/250
D	Prob. rhombic	800	300	
E	Prob. rhombic	800	300	

- 40 -

TOP SECRET


TOP SECRET

PIC/JR-8/59

Item Letter	Configuration	Masts	Height of Mast (feet)
A	Horizontal dipoles	2-4	
F	Unknown	At least 25	

IV. OVERHEAD POWER AND/OR COMMUNICATION LINES

No visible power lines supporting the installation appear on [] photography. A power line appearing on 1956 ground photography leads past the southwest corner of the installation, but it cannot be determined whether this line supports the installation.




MAP DATA:

ATMP

AMS Series N 501 Sheet No. NN 37-1

COLLATERAL REPORTS



COORDINATES: 55°56'N/37°40'E

25X1C

- 41 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 30

KUPAVNA ANTENNA FARM

I. GENERAL

Kupavna Antenna Farm is located 17 nautical miles east of Moscow and just south of the Moscow/Gorky rail line (Figure 24). This farm, which reportedly extends along the rail line in the vicinity of Kupavna,




FIG 24. LOCATION MAP

cannot be identified on [] aerial photography and probably did not exist at that time. Ground photography of 1955-56 shows this farm to include one control building, a support-type building, three guyed steel towers, and numerous stick masts.

II. STRUCTURES

Ground photography of 1955 shows two structures, the largest of which is the control building, reported to be 200 by 75 feet. This building,

- 42 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

possibly T-shaped, varies from two to three stories in height. The two-story section, which is the major portion of the building, has approximately eight air vents on the roof. The support-type building is a single-story structure located adjacent to the control building (Figure 25).




FIG 25. KUPAVNA ANTENNA FARM View of the control building, one guyed steel lattice mast, and 40 stick masts (1955).

III. ANTENNAS

Ground photography of 1955 shows that the farm contains three tall sectional guyed steel lattice masts oriented in a straight line and reported to be 250 to 350 feet high (Figure 26). Crossarms are positioned at the top of each mast to support probable horizontal dipole antennas. Spreaders are noted between the horizontal wires. There are also over 50 stick masts in the area. The apparent arrangement of some of these masts indicates the presence of possible rhombic antennas. There are reported to be four ladder-type steel masts within the area, but they cannot be identified on the ground photography.

- 43 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

FIG 26. KUPAVNA ANTENNA FARM View of three guyed steel towers (1955).

IV. OVERHEAD POWER AND/OR COMMUNICATIONS LINES
Ground photography shows a multiwire telephone or telegraph line and a power line. No connection between the site and these facilities is visible, but one probably exists.

25X1D

25X1C

TOP SECRET

TOP SECRET

PIC/JR-8/59

MAP DATA:
ATMP

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°45'N/38°06'E

25X1D

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 31

ELEKTROSTAL RADIO STATION

I. GENERAL

Elektrostal Radio Station is located 26 nautical miles (nm) east of Moscow, 4.75 nm south of Noginsk, and 1.3 nm west of Elektrostal (Figure 27). The station, which covers approximately 225 acres (3,800 by 2,600 feet), is enclosed by a fence and served by an all-weather road. Aerial photography shows the station to consist primarily




FIG 27. LOCATION MAP




FIG 28. LINE DRAWING OF ELEKTROSTAL RADIO STATION

TOP SECRET

TOP SECRET

PIC/JR-8/59

of a control building, a possible cooling tower, three buildings probably housing antenna coupling/tuning equipment, and four tall guyed steel masts (Figures 28 and 29).

II. STRUCTURES

The following is a tabulation of all structures in the area as of (item numbers are keyed to Figure 28).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	-	-	-
1a	Base	2 or 3	Valley	185 x 70
1b	Wing	2 or 3	Valley	80 x 55
2	Probable support building	1	-	55 x 35
3	Probable support building	1	-	90 x 55
4	Possible cooling tower	1	-	35 x 35
5	Guardhouse	1	-	55 x 35
6, 7, 8	Coupling/tuning houses	1	-	-

III. ANTENNAS

Aerial photography shows the four guyed steel masts, approximately 740 feet high and 900 feet apart, to be located in a straight line and oriented in an approximate north-south direction. A small building probably housing coupling/tuning equipment is located in line with and midway between each of these masts. The location of these coupling/tuning buildings may indicate that center-fed horizontal-dipole-type antennas are supported by the masts. Collateral information as late as 1956 reports that wires are suspended between the tops of the four masts.

TOP SECRET

TOP SECRET [REDACTED]

PIC/JR-8/59




FIG 29. ELEKTROSTAL RADIO STATION

- 48 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59



MAP DATA:
ATMP- [REDACTED]

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°46'N/38°25'E

25X1D

- 49 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 35

BYKOVO RADIO STATION

1. GENERAL

Bykovo Radio Station is located about 17 nautical miles east-southeast of Moscow and immediately adjacent to the west side of Bykovo Airfield (Figure 30). The station is enclosed by a fence 620 feet square and covers an area of approximately 9 acres. It is served by an all-weather road. Aerial photography [REDACTED] shows the station to consist of a control building, a cooling pond, a guardhouse, several other small structures, and several masts (Figure 31). No overhead power and/or communication lines can be identified on the photography.




FIG 30. LOCATION MAP

- 50 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59




FIG 31. BYKOVO RADIO STATION

- 51 -

TOP SECRET [REDACTED]

TOP SECRET

PIC/JR-8/59




FIG. 32. LINE DRAWING OF BYKOVO RADIO STATION

II. STRUCTURES

The following is a tabulation of major structures within the station (item numbers are keyed to Figure 32).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	1	Complex	50 x 45
2	Cooling pond	-	-	30 dia
3	Support-type building	1	-	25 x 25
4	Support-type building	1	-	25 x 20
5	Guardhouse	1	-	15 x 15

- 52 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

III. ANTENNAS

The [redacted] photography shows one mast approximately 65 feet high located in the center of an elliptical pattern of approximately 25 evenly spaced masts each 20 feet high. The diameter of this pattern of masts is 200 feet.

Collateral information of 1954-1958 indicates that this station may have been altered [redacted]. According to this information, the station has from six to ten masts estimated to be 40 feet high, linked together in pairs, and supporting medium-frequency dipole antennas.

MAP DATA:

ATMP [redacted]

COLLATERAL REPORTS:

COORDINATES: 55°37'N/38°05'E

25X1D

25X1D

- 53 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 37

BIRYULEVO ANTENNA FARM

Biryulevo Antenna Farm is located 10 nautical miles south of Moscow in the vicinity of the towns of Lenino, Biryulevo, and Tsaritsino (Figure 33). It is situated in a partially wooded area west of the Moscow/Kashira highway. The poor resolution and partial cloud cover of [redacted] aerial photography




FIG. 33. LOCATION MAP

prohibit the identification of any antenna patterns or actual site limits; however, a T-shaped control building, a support-type building, and a possible tent area can be identified (Figure 34). A military area is located immediately north of the farm site. The antenna farm does not appear

- 54 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 34. BIRYULEVO ANTENNA FARM

- 55 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

on [] photography. It is reported that the farm began operation in May 1949. Collateral information between 1947 and 1951 reports this site to contain numerous stick masts, some of which support rhombic and squirrel-cage-type antennas.

MAP DATA:
ATMP []

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°36'N/37°41'E

25X1D

- 56 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 40

DOMODEDOVO ANTENNA FARM

I. GENERAL

Domodedovo Antenna Farm is located 17 nautical miles south of Moscow, along the east side of the Moscow/Kashira highway and on the northern outskirts of Domodedovo (Figure 35). The farm, which is enclosed by a fence, covers an area of approximately 500 acres and is served by an all-weather road. There are approximately 25 structures of various sizes and many stick masts within the area. Several structures, including a control building, are visible on [] aerial photography. Aerial photographs




FIG. 35. LOCATION MAP

- 57 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

raphy of [] and ground photography of 1958 reveal that additional housing and support buildings had been constructed [] (Figure 36).



FIG. 36. DOMODEDOVO ANTENNA FARM. View of 4 support-type buildings and 20 guyed stick masts (1958).

II. STRUCTURES

The following is a tabulation of the structures within the area as of [] (item numbers are keyed to Figure 37).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	2	Complex	60 x 35
2	Unidentified	-	-	20 x 15
3	Support building	-	-	50 x 30
4	4 barracks	2	Hip	55 x 30
5	Support building	1	-	50 x 35
6	Support building	1	-	30 x 20

- 58 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
7	3 dwellings	1	Gable	45 x 25
8	Possible administration building	2	Hip	50 x 35
9	Barracks	2	Hip	80 x 40
10	Support building	1	Complex	95 x 45
11	Support building	1	Complex	110 x 50
12	Support building	-	-	50 x 20
13	Support building	-	Gable	80 x 40
14	Support building	-	Gable	50 x 20
15	Support building	-	-	55 x 20
16	Unidentified	-	-	60 x 30




FIG. 37. LINE DRAWING OF DOMODEDOVO ANTENNA FARM

- 59 -

TOP SECRET

TOP SECRET [REDACTED]

PIC/JR-8/59



FIG 38. DOWODEDOVO ANTENNA FARM. View of 14 guyed stick masts and 30 self-supporting stick masts in a 10-10-10 pattern (1958).




FIG 39. DOWODEDOVO ANTENNA FARM. View of the control building, 20 guyed stick masts, and a microwave parabola mounted on top of a guyed steel mast (1958).

- 60 -


TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

111. ANTENNAS

Aerial photography [REDACTED] shows no antenna patterns, owing to its poor resolution. Ground photography of 1958 shows numerous guyed stick masts and the following types of antennas: rhombic antennas, horizontal cage antennas, and an arrangement of 30 self-supporting stick masts in a 10-10-10 pattern. At least one microwave parabola mounted at the top of a guyed sectional steel mast also appears on 1958 photography. (Figures 36, 38, and 39).



25X1C

MAP DATA:

ATMP [REDACTED]

COLLATERAL REPORTS:

COORDINATES: 55°28'N/37°45'E

25X1D

TOP SECRET [REDACTED]

NUMBER 46

BUTOVO ANTENNA FARM

I. GENERAL

Butovo Antenna Farm is located 13 nautical miles south of Moscow and adjacent to the southwest corner of Butovo (Figure 40). This farm, which covers approximately 640 acres, is enclosed by a fence and served by an all-weather road. Aerial photography [REDACTED] and ground photography of 1957 show that the site consists primarily of a central control building, two subordinate control buildings, several smaller buildings, 27 fishbone antenna arrays, and several possible rhombic antennas.




FIG 40. LOCATION MAP

II. STRUCTURES

The following is a tabulation of the major structures within the site [REDACTED] (item numbers are keyed to Figure 42).

- 62 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59



FIG 41. BUTOVO ANTENNA FARM

- 63 -

TOP SECRET [REDACTED]

TOP SECRET

PIC/JR-8/59




FIG. 42. LINE DRAWING OF BUTOVO ANTENNA FARM

- 64 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Central control building	2 or 3	Complex	90 x 80
2	Control building	2 and 3	Hip	75 x 50
3	Control building	2 or 3	Valley	-
3a	Base	2 or 3	-	50 x 40
3b	Stem	2 or 3	-	60 x 30
4	Support building	1	Gable	45 x 20
5	Support building	1	Gable	25 x 25
6	Support building	1	Gable	35 x 20
7	Support building	1	Gable	85 x 25

III. ANTENNAS

The antenna field appearing on [redacted] photography contains 15 fishbone antennas, of which 12 are of the two-bay day antenna type and 3 are of the one-bay night antenna type. The three one-bay night types are constructed adjacent to three of the two-bay day types (see the following table, item letters F, J, and L). Approximately 20 tall stick masts possibly supporting rhombic-type antennas appear on 1952 ground photography. The following table gives data on the fishbone antennas (item letters are keyed to Figure 42).

Item Letter	Antenna Type	Dimensions (feet)*	
		Length	Width
A	Two-bay day	320	60
B	Two-bay day	320	60
C	Two-bay day	320	60
D	Two-bay day	320	60
E	Two-bay day	320	60
F	Two-bay day	320	60
	One-bay night	320	60

Table continued on next page

* As determined from pole excavation scars; the poles cannot be seen on the photography.

- 65 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

(CONTINUED)

Item Letter	Antenna Type	Dimensions (feet)	
		Length	Width
G	Two-bay day	320	60
H	Two-bay day	320	60
I	Two-bay day	320	60
J	Two-bay day	320	60
	One-bay night	320	96
K	Two-bay day	320	60
L	Two-bay day	320	60
	One-bay night	320	60

25X1D

25X1D

MAP DATA:

ATMP

COLLATERAL REPORTS:

COORDINATES: 55°32' N/37°33' E

25X1D

- 66 -

TOP SECRET


TOP SECRET

PIC/JR-8/59

NUMBERS 49, 50, 53, and 54

COMMUNICATIONS COMPLEX NEAR DESNA

A communications complex is located along the Moscow/Kaluga highway, 18 nautical miles (nm) southwest of Moscow (Figure 43). The complex includes an operational area, with four separately fenced radio stations, extending east of the Moscow/Kaluga highway between the towns of



- 67 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 44. LINE DRAWING OF COMMUNICATIONS COMPLEX NEAR DESNA

Desna and Vatutinki; and a general support area, located adjacent to the west side of the highway at a point opposite the operational area. The over-all complex covers 1,369 acres (Figures 44 and 45).

The four radio stations are designated in this report as stations 49, 50, 53, and 54 (Figure 44). A comparison of aerial photography shows that stations 49, 50, and 54 were present in [redacted] and that Station 53 was constructed later. The support area is not covered by [redacted] photography. Between [redacted] Station 49, the largest of

- 68 -
TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 45. COMMUNICATIONS COMPLEX NEAR DESNA

It should be noted that this oblique photograph is turned 180° from FIG. 44.

- 69 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

the four, had an increase in the number of structures, but the antenna field pattern appears unchanged. Station 50 had an increase in the number of structures, but, although the antenna field pattern appears slightly changed, nothing indicates any change in the number and type of antennas. Station 54 had an increase in the number of structures, and the field pattern indicates the construction of additional antennas.

The presence of only rhombic and fishbone antennas is indicated by the pattern of tree clearings. The absence of cooling facilities, the existence of fishbone receiving antennas, and the orientation diversity of the rhombic antennas indicate that this is a probable receiving complex. A Krug site, not considered a part of this complex, is located 2 nm south of Station 49 (Figure 45).

SUPPORT AREA

I. GENERAL

The support area is on the west side of the Moscow/Kaluga highway, 17.5 nm southwest of Moscow (Figures 43 and 44). The support area, a fenced area of 135 acres (2,800 by 2,100 feet), probably serves all four radio stations (Figure 46). It includes 69 buildings, one of which is under construction, three unidentified areas, an athletic field, and a network of paved streets. Three streets connect the area to the Moscow/Kaluga highway. A road leads west from the southwest fence corner to an elaborate housing area which is not believed to be part of the communications complex.

II. STRUCTURES

The structures existing as of 1956 are listed in the following tabulation (item numbers are keyed to Figure 46).

- 70 -
TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 46. LINE DRAWING OF SUPPORT AREA

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Administration-type building, U-shape	2 1/2	Hip	130 x 35 (main) 35 x 20 (wings)
2	Administration-type building	1	Hip	115 x 45
3	Athletic field	-	-	330 x 200
4	Administration-type building, U-shape	2	Hip	120 x 35 (main) 35 x 20 (wings)
5	Barracks	2	Hip	145 x 40
6	Barracks	1	Hip	145 x 40
7	Barracks	1	Hip	145 x 40
8	Probable apartment building	1	Gable	200 x 35

- 71 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

(CONTINUED)

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
9	Probable apartment building	1	Gable	200 x 35
10	Probable apartment building	1	Gable	200 x 35
11	Support building	1	Gable	110 x 20
12	Support building	1	Gable	30 x 25
13	Probable apartment building	1	Gable	200 x 35
14	Probable apartment building	1	Gable	200 x 35
15	Probable apartment building	1	Gable	200 x 35
16	Probable security building	1	Gable	165 x 65
17	Support building	1	Gable	80 x 25
18	Support building	1	Shed	15 x 10
19	Support building	1	Shed	20 x 10
20	Support building	1	Gable	40 x 25
21	Probable apartment building	1	Gable	200 x 35
22	Probable apartment building	1	Gable	200 x 35
23	Support building	1	-	30 x 30
24	Barracks	1	Hip	145 x 40
25	Support building	1	Gable	20 x 15
26	Support building	1	Gable	75 x 20
27	Support building	1	Gable	75 x 20
28	Support building	1	Gable	110 x 35
29	Building U/C	-	-	75 x 75
30	Unidentified area	-	-	650 x 150
31	Unidentified area	-	-	125 x 100
32	Support building	1	Gable	30 x 25

- 72 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

(CONTINUED)

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
33	Support building	1	Gable	80 x 35
34	Support building	1	Gable	60 x 35
35	Support building	1	Hip	165 x 45
36	Support building	1	Gable	120 x 25
37	Administration-type building, U-shape	1 1/2	Hip	165 x 65 (main) 50 x 35 (wings)
38	Barracks	1	Hip	100 x 65
39	Barracks	1	Hip	100 x 65
40	Support building	1	Gable	30 x 25
41	Barracks	1	Hip	130 x 35
42	Barracks	1	Gable	130 x 30
43	Possible barracks	1	Gable	110 x 40
44	Support building	1	Gable	80 x 40
45	Support building	1	Gable	30 x 25
46	Support building	1	Gable	30 x 20
47	Support building	1	Gable	30 x 25
48	Support building	1	Gable	40 x 30
49	Support building	1	Gable	20 x 15
50	Support building	1	Gable	20 x 15
51	Possible barracks	1	Gable	110 x 35
52	Support building	1	Gable	30 x 25
53	Support building	1	Gable	35 x 30
54	Support building	1	Gable	50 x 25
55	Possible barracks	1	Gable	120 x 35
56	Support building	1	Gable	25 x 20
57	Support building	1	Gable	130 x 25
58	Support building	1	Gable	165 x 25
59	Possible barracks	1	Hip	130 x 30
60	Unidentified area U/C	-	-	460 x 200
61	Barracks	1	Gable	130 x 40

- 73 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

(CONTINUED)

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
62	Support building	1	Gable	80 x 40
63	Support building	1	Hip	75 x 40
64	Support building	1	Gable	35 x 25
65	Possible barracks	2	Gable	130 x 45
66	Support building	1	Gable	40 x 25
67	Support building	1	Gable	50 x 25
68	Support building	1	Gable	130 x 35
69	Support building	1	Gable	130 x 25
70	Support building	1	Gable	30 x 25
71	Possible barracks	1	Gable	115 x 40
72	Support building	1	Gable	30 x 25
63	Support building	1	Hip	80 x 30
74	Support building	1	Hip	95 x 25

STATION 49

I. GENERAL

Station 49 (Figure 47), covering a fenced area of approximately 527 acres (5,600 by 4,100 feet), is located 18 nm southwest of Moscow. The area is served by a 25-foot-wide paved road which leads east from the Moscow/Kaluga highway. Aerial photography shows the station to include a control building, a possible semiburied structure under construction, and numerous other buildings. Ground scars in the area indicate that some of the buildings had been recently constructed. A tent area is probably used to house construction workers. The antenna field contains at least 18 probable rhombics.

II. STRUCTURES

The structures in Station 49 are listed in the following tabulation (item numbers are keyed to Figure 47).

- 74 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	2	Hip	200 x 50
2	Support building	1	Shed	15 x 15
3	Support building	1 1/2	Hip	50 x 50
4	Support building	1	Gable	45 x 40
5	Support building	1	Gable	50 x 25
6	Tent area	-	-	230 x 130
7	Support building	1	Hip	60 x 30
8	Unidentified building	-	-	50 x 40
9	Unidentified building (poss. U/C)	-	-	130 x 90
10	Unidentified area	-	-	300 x 170
11	Possible semiburied structure U/C	-	-	70 x 50
12	Support building	1	Gable	80 x 35
13	Support building	1	Gable	40 x 40
14	Support building	1	Gable	110 x 30
15	Support building	1	Gable	110 x 30
16	Support building	1	Gable	120 x 35
17	Support building	1	Gable	50 x 30
18	Support building	1	Gable	110 x 30
19	Support building	1	Gable	50 x 35
20	Support building	1	Gable	55 x 40
21	Support building	1	Gable	145 x 45
22	Unidentified area	-	-	265 x 165

III. ANTENNAS

The antenna field almost encircles the control building. The field is covered with timber, and the only clearings are the locations of the rhombics and their feedlines. There are 18 diamond-shaped clearings, one of which is occupied by the tent area (Figure 47, Item 6).

- 75 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Ground scars indicating the position of masts and guy-wire anchor bases can be identified in 8 of the diamond-shaped clearings. These scars remained unchanged. Two types of antenna patterns are formed by the positioning of these ground scars (Figure 48). The antenna configurations shown on Figure 48 are only suggested wiring diagrams. It is also possible, however, that the exterior rhombic was constructed first and then removed or that the interior was constructed first and then removed. These configurations with one rhombic antenna within another have not previously been noted on other aerial photography of the Soviet Bloc.

It is interesting to note that rhombic antennas with one smaller rhombic within a larger rhombic are used at the high-frequency transmitter station at [redacted]. Each aerial of the pair covers a frequency range of about 2.5:1, and between them they cover virtually all the frequencies likely to be used on one circuit. This type of rhombic may also be used for circuits where high gain is required, particularly at the lower frequencies and at low angles.

Type I (Figure 48) is a double-end-pole rhombic with a smaller double-end-pole rhombic located within its parameters. Type II (Figure 48) is a single end-pole rhombic with a smaller double-end-pole rhombic located within its parameters. The item letters in the following tabulations are keyed to Figure 47. All dimensions are expressed in feet.

ANTENNAS

Item Letter	Type	Dimensions				End Mast Separation	Tilt Angle
		Major Axis Ex	Major Axis In	Minor Axis Ex	Minor Axis In		
E	II	760	430	350	350	50	
F	II	760	430	365	365	50	
G	II	725	430	365	365	50	
H	I	760	430	365	365	50	
I	I	775	420	340	350	50	
J	I	725	430	365	365	50	
K	II	695	420	360	360	50	
L	II			360	360	50	

Note: Exterior (Ex) dimensions are for large antennas; interior (In) dimensions are for small antennas.

- 76 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 47. LINE DRAWING OF STATION 49

RHOMBIC CLEARINGS

Item Letter	Dimensions *	
	Major Axis	Minor Axis
U	825	430
C	925	430
D	890	365
M	890	365
N	890	365
O	820	365
Q	925	430
R	860	365
S	925	365
T	925	365

* Over-all lengths and widths for the diamond-shaped clearings. The rhombic antennas that may be located in these clearings would have smaller dimensions. The exact antenna patterns, however, cannot be seen.

- 77 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

OTHER CLEARINGS

Item Letter	Shape	Dimensions		Utilization
		Length	Width	
A	Rectangular	630	365	Cultivated field
P	Linear	1,325	65	U-1
U	Rectangular	560	400	U-1
V	Rectangular	560	230	Cultivated field
W	Rectangular	1,090	265	U-1
X	Triangular	1,150	725	Cultivated field
Y	Rectangular	430	200	Power construction area
Z	Rectangular	330	230	Feed-line junction area




FIG 48. SUGGESTED RHOMBIC PATTERNS, STATION 49

- 78 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

STATION 50

1. GENERAL

Station 50 is located 17.5 nm southwest of Moscow (Figure 43) and immediately north of Station 49 (Figure 44). Station 50 covers a fenced area of 306 acres (3,700 by 3,600 feet) and is served by a 25-foot-wide paved road which leads east from the Moscow/Kaluga highway. Photography [redacted] reveals a total of 21 structures, including a control building at the terminus of the service road. Photography [redacted] reveals at least 11 rhombic-shaped clearings in the antenna field. On [redacted] photography the antenna field is partially overgrown with low vegetation, and none of the previous rhombic-shaped clearings is visible (Figures 49 and 50). No masts are visible on the [redacted] photography.




FIG 49. OBLIQUE VIEW OF STATION 50

- 79 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

11. STRUCTURES

The structures as of [] are listed in the following tabulation (item numbers are keyed to Figure 50).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	2	Hip	135 x 65
2	Support building	1	Gable	35 x 30
3	Unidentified area	-	-	150 x 90
4	Support building	1	-	15 x 15
5	Support building	1	Gable	60 x 30
6	Support building	1	Shed	15 x 15
7	Support building	1	-	20 x 15
8	Support building	1	Gable	45 x 25
9	Support building	1 1/2	Hip	100 x 65
10	Support building	1	-	15 x 15
11	Support building	1	Gable	65 x 20
12	Security building	1	-	30 x 30
13	Building U/C	-	-	130 x 25
14	Support building	1	Gable	25 x 20
15	Athletic field	-	-	470 x 200
16	Support building	1	Hip	65 x 25
17	Support building	1	Gable	50 x 30
18	Support building	1	Gable	30 x 30
19	Unidentified area	-	-	40 x 30
20	Support building	2	Hip	100 x 65
21	Support building	1	Gable	45 x 25

111. ANTENNAS

Aerial photography of [] shows 11 diamond-shaped clearings which may contain rhombic antennas, but the masts are not visible. Aerial photography [] shows that these clearings had been

- 80 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 50. LINE DRAWING OF STATION 50

overgrown since [] with low vegetation, which prevents determination of the antenna pattern, although it would not interfere with operation. One of the cleared areas on this later photography (Figure 50, Item A) is an athletic field. A rectangular cleared area (Figure 50, Item G) is located near the southeast corner of the installation and is connected

- 81 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

to the control building by a trail, but it cannot be determined whether an antenna is located in the clearing.

The locations of the clearings as listed in the following tabulation are keyed to the item letters on Figure 50. The clearings are shown as they appear on [] aerial photography. The orientation of the probable rhombics and the major and minor axis dimensions are from [] photography.

Item Letter	Major Axis (feet)	Minor Axis (feet)
B	825	430
C	720	360
D	720	360
E	620	290
F	900	540
H	720	360
I	720	360
J	720	360
K	720	360
L	720	360

25X1D

STATION 53

I. GENERAL

Station 53 (Figure 51) is located 17.5 nm southwest of Moscow and 100 feet east of Station 50 (Figures 43 and 44). Station 53 covers a fenced area of 129 acres (2,450 by 2,300 feet) and is served by a 25-foot-wide paved road from the Moscow, Kaluga highway. The station was constructed between [] There are four structures in the area, one of which is a control building. [] the area was covered by timber, but after []

- 82 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 51. LINE DRAWING OF STATION 53

clearings were made for antennas and feedlines. There are seven rectangular-shaped clearings which appear to be for fishbone-type antennas.

11. STRUCTURES

The structures as of [] are listed in the following tabulation (item numbers are keyed to Figure 51).

- 83 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building, T-shaped	1	Hip	100 x 35 (main) 45 x 35 (wing)
2	Support building	1	Hip	35 x 35
3	Guardhouse	1	Gable	25 x 20
4	Support building	1	Gable	35 x 25

III. ANTENNAS

The rectangular clearings shown on Figure 51 may be the locations of fishbone-type antennas, but the masts are not visible. Two other clearings (Figure 51, items D and I) have apparent feed line clearings leading to the control building, but the type of antenna that may be located in these clearings cannot be determined. The fishbone-type antenna clearings as of [redacted] are listed in the following tabulation (item letters are keyed to Figure 51).

Item Letter	Clearing Length (feet)	Clearing Width (feet)	Approx. Azimuth Orientation (Degrees)
A	430	265	35/215
B	430	265	20/200
C	350	300	
E	430	265	
F	285	230	
G	365	265	
H	660	315	

STATION 54

I. GENERAL

Station 54 (Figure 52) is located 17 nm southwest of Moscow, adjacent to Station 53 (Figures 43 and 44). Station 54 covers a fenced area of 272

- 84 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

acres (3,700 by 3,200 feet) and is served by the same paved road that serves Station 53. Station 54 contains numerous structures, including a control building. There was an increase in the number of structures from [redacted] as shown by the photography of those years, but the antenna field was relatively unchanged. There are seven rectangular-shaped clearings which appear to be for fishbone-type antennas, and there are six larger cleared




FIG. 52. LINE DRAWING OF STATION 54

- 85 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

areas which may contain additional antennas, the types of which cannot be determined.

II. STRUCTURES

The structures [redacted] are listed in the following tabulation (item numbers are keyed to Figure 52).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building, L-shaped	2	Hip	100 x 50 (main) 50 x 35 (wing)
2	Support building	1	Gable	15 x 15
3	Support building	1	Gable	30 x 20
4	Building U/C	-	-	100 x 65
5	Support building	1	Gable	45 x 20
6	Support building	1	Gable	35 x 35
7	Support building	1	Gable	40 x 20
8	Support building	1	-	30 x 25
9	Support building	1	Gable	25 x 15
10	Building U/C	-	-	35 x 35
11	Guardhouse	1	Hip	30 x 30
12	Unidentified area	-	-	50 x 40
13	Possible athletic field	-	-	370 x 260
14	Tent area (20 tents)	-	-	-

III. ANTENNAS

There are seven rectangular clearings within the partially wooded antenna field which may be the locations of fishbone-type antennas. There are six larger cleared areas in the antenna field which may contain many more antennas, but no masts are visible. The antenna field pattern remained almost unchanged from [redacted].

The fishbone-type antenna clearings as of [redacted] are listed in the following tabulation (item letters are keyed to Figure 52).


- 86 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item Letter	Clearing Length (feet)	Clearing Width (feet)
B	400	230
C	400	230
D	400	230
E	430	230
F	400	230
J	400	230
K	400	135



NEXT DATA:

COLLATERAL REPORTS:

25X1C

- 87 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COORDINATES: 55°29'N/37°20'E - (Station 49)
 55°30'N/37°21'E - (Station 50)
 55°30'N/37°22'E - (Station 53)
 55°30'N/37°23'E - (Station 54)

25X1D

TOP SECRET

PIC/JR-8/59




FIG. 54. LINE DRAWING OF KOMMUNARKA ANTENNA FARM

II. STRUCTURES

The following is a tabulation of the structures within the area as of [redacted] item numbers are keyed to Figure 54).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	2 or 3	Valley	-
1a	Base	2 or 3	-	145 x 35
1b	Stem	2 or 3	-	70 x 45
1c	Wing	2 or 3	-	25 x 25
2	Support-type building	2 or 3	Hip or gable	70 x 45
3	Support-type building	2 or 3	Hip or gable	70 x 45
4	Support-type building	2 or 3	Hip or gable	70 x 45
5	Support-type building	2 or 3	Hip or gable	45 x 45

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 57

KOMMUNARKA ANTENNA FARM

I. GENERAL

Kommunarka Antenna farm is located 12 nautical miles (nm) south-southwest of Moscow, 3 nm west-northwest of Butovo, and adjacent to the Kommunarka Collective Farm (Figure 53). The antenna farm is enclosed by a fence and covers 30 acres. Aerial photography [redacted] shows that a control building and four support-type buildings are the major structures within the area. No masts or towers can be identified because of the poor resolution and small scale of the photography.




FIG. 53. LOCATION MAP

TOP SECRET

TOP SECRET

PIC/JR-8/59

III. ANTENNAS

The [redacted] aerial coverage reveals no antenna patterns, but collateral information between 1946 and 1949 reports the presence of 15 masts each 25 meters high, 75 masts each 15 meters high, and approximately 200 masts each 8 meters high.

MAP DATA:

ATMP [redacted]

COLLATERAL REPORTS:

COORDINATES: 55°34'N/37°28'E

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 58

TEPLY STAN ANTENNA FARM

I. GENERAL

Teply Stan Antenna Farm, covering approximately 170 acres, is located 8.5 nautical miles south-southeast of Moscow at the 19 kilometer mark and on the east side of the Moscow/Kaluga highway (Figure 55). The antenna farm can be identified on [] aerial photography and on 1957 ground photography. Owing to poor resolution, only major structures can be identified on the [] aerial photography; however, numerous stick masts can be identified on 1957 ground photography. The absence of cooling facilities and the existence of a fishbone receiving antenna indicate that this is a probable receiving station.




FIG 55. LOCATION MAP

TOP SECRET

TOP SECRET

PIC/JR-8/59

II. STRUCTURES

The following is a tabulation of the more prominent structures identified in this area on [] photography (item numbers are keyed to Figure 56). No control building can be identified and no cooling facilities are noted. Structurally, the area seems to have undergone almost a total change since the [] aerial photography.

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Barracks or administration building	2	Hip	70 x 50
2	Barracks or administration building	2	Hip	70 x 50
3	Unidentified	1	-	30 x 30
4	Unidentified	1	Gable	50 x 30
5	Six possible housing units	1	-	25 x 25
6	Unidentified	1	-	20 x 20
7	Barracks or administration building	2	Hip	70 x 50
8	Barracks or administration building	2	Hip	70 x 50
9	Unidentified	-	-	-
10	Unidentified	-	-	-
11	Unidentified	-	-	-
12	Guardhouse	1	-	10 x 10

III. ANTENNAS

At least 110 stick masts can be identified on 1957 ground photography (Figure 57). All poles appear to be approximately 40 feet high, except one which is 80 feet high. A portion of at least one 5-3-3-5 fishbone-type antenna can be identified (Figure 58). At least one horizontal cage-type antenna can also be identified. A count made on [] aerial photography reveals approximately 25 poles; thus, a considerable change in antenna configurations had been made [].

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 56. LINE DRAWING OF TEPLY STAN ANTENNA FARM

IV. OVERHEAD POWER AND OR COMMUNICATIONS LINES

Figure 57 shows a multiwire telephone or telegraph line and a power line paralleling the Moscow/Kaluga highway in front of the radio station. Although not visible, a connection probably exists between the site and these facilities.

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 57. TEPLY STAN ANTENNA FARM. Aerial view of antenna farm along Moscow/Kaluga highway. Note power and communication lines along road.




FIG 58. TEPLY STAN ANTENNA FARM. An example of a portion of a fishbone antenna arranged in a 5-3-3-5 pattern.

TOP SECRET

TOP SECRET

PIC/JR-8/59

25X1D

Ground Photography

25X1C

MAP DATA:

ATMP

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°37'N/37°31'E

25X1D

TOP SECRET

PIC/JR-8/59



FIG. 60. VORONTSOVO ANTENNA FARM. View of one control building with support buildings (1951)

II. STRUCTURES

The following is a tabulation of the structures within the area as of [redacted] (item numbers are keyed to Figure 61).

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Control building	2 or 3	Complex	
2	Support building	1 or 2	Gable	
3	Support building	1 or 2	-	
4	Support building	-	-	30 x 30
5	Support building	2	-	45 x 45
6	Support building	2	Gable	65 x 45
7	Guardhouse	1 or 2	-	20 x 20
8	Unidentified	1 or 2	-	
9	Guardhouse	1 or 2	Gable	30 x 20
10	Unidentified	-	-	50 x 40
11	Unidentified	1 or 2	Gable	55 x 25
12	Control building	1 and 2	Gable	100 x 50
13	Cooling pond	-	-	35 dia.
14	Cooling pond	-	-	35 dia.
15	Support building	1 or 2	Gable	100 x 30

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 59

VORONTSOVO ANTENNA FARM

I. GENERAL

Vorontsovo Antenna Farm is located 6.5 nautical miles (nm) south-west of Moscow between the Moscow/Kaluga and Moscow/Kiev highways and less than one nm west of Vorontsovo (Figure 59). This antenna farm, situated immediately adjacent to a military area, is enclosed by a




FIG. 59. LOCATION MAP

fence, is road-served, and covers approximately 78 acres. Aerial photography [redacted] Figure 62) and ground photography of 1955-56 show that this farm had been enlarged since [redacted] and that as [redacted] it included two control buildings, each with an adjacent cooling pond, six support buildings, and probable rhombic and horizontal cage-type antennas (Figure 60).

TOP SECRET

25X1

TOP SECRET

PIC/JR-8/59




FIG. 61. LINE DRAWING OF VORONTSOVO ANTENNA FARM

TOP SECRET

TOP SECRET

PIC/JR-8/59



FIG 62. VORONTSOVO ANTENNA FARM

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG 63. VORONTSOVO ANTENNA FARM. Near view showing approximately 35 guyed stick masts (1957)

III. ANTENNAS

Many ground scars within the area indicate the presence of antennas, but because of poor resolution antenna types or antenna patterns cannot be identified on the aerial photography. Ground photography of 1955-57 shows approximately 100 guyed stick masts (Figure 63). Horizontal cage antennas are extended between some masts, and the position of other masts indicates probable rhombic antenna patterns, some of which are of the double-end-pole type. Collateral reports, dated from 5 March 1951 to 20 February 1957 indicate that the area contains approximately 200 masts, varying in height from 45 to 60 feet, forming double-end-pole rhombic and squirrel-cage antennas.

TOP SECRET

TOP SECRET

PIC/JR-8/59

25X1D

25X1C

MAP DATA:
ATMP

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°39'N, 37°31'E

25X1D

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 62

TOLSTOPALTSEVO ANTENNA FARM

I. GENERAL

Tolstopaltsevo Antenna Farm is located 16 nautical miles (nm) west-southwest of Moscow and 2.5 nm west-northwest of Vnukovo Airfield (Figure 64). The area is probably enclosed by a fence and contains approximately 86 acres (2,500 by 1,500 feet). A comparison of aerial photography shows that since the antenna farm had more than doubled in size and consisted as of a control building, guardhouse, and two possible support-type buildings (Figure 65).




FIG 64. LOCATION MAP

TOP SECRET

TOP SECRET




FIG. 65. TOLSTOPALTSEVO ANTENNA FARM

II. STRUCTURES

The following is a tabulation of the structures within the area as of (item numbers are keyed to Figure 66).

Item No.	Identification	Stories	Roof Type	Approx. Dimensions (feet)
1	Control building	-	-	55 x 45
2	Guardhouse	1	Shed	15 x 15
3	Possible support-type building	1	Gable	40 x 20
4	Possible support-type building	1	-	30 x 20

- 104 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

III. ANTENNAS

There are at least 14 masts within the area. They cannot be seen on aerial photography, but their existence is indicated by the characteristic pattern made by the mast base and four guy-wire anchor bases. It has been reported that the area contains at least 10 tall steel masts and 15-20 short masts.




FIG. 66. LINE DRAWING OF TOLSTOPALTSEVO ANTENNA FARM

- 105 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

25X1D

MAP DATA:

25X10

COLLATERAL REPORTS:

25X10

COORDINATES: 55°36'N/37°13'E

25X1D

- 106 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 67

CHERNEVO RADIO STATION

I. GENERAL

Chernevo Radio Station is located just south of the Moscow/Istra highway at a point 12.5 nautical miles (nm) west of Moscow and 0.5 nm west of Chernovo (Figure 67). The station is fenced and covers approximately 25 acres. Aerial photography and ground photography of 1953 show this site to contain approximately 20 buildings and 4 stick masts.




FIG. 67. LOCATION MAP

II. STRUCTURES

The poor resolution and partial cloud cover of the photography prohibit the positive identification of some structures. These structures

- 107 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

although measured, are identified only as possible buildings. The following is a tabulation of the more prominent structures within the area as of [] (item numbers are keyed to Figure 68).

Item No.	Identification	Stories	Roof Type	Approx. Dimensions (feet)
1	Administration-type building	-	-	210 x 90 (over-all)
2	Barracks-type building	2 1/2	Hip	135 x 90 (over-all)
3	Dwelling	1	Gable	40 x 20
4-9	Dwellings	1	Gable	40 x 20
10	Building (T-shape)	-	-	165 x 55 (main) 55 x 40 (wing)
11	Building (T-shape)	-	-	145 x 40 (main) 50 x 40 (wing)
12	Building (L-shape)	-	-	55 x 35 (main) 35 x 15 (wing)
13	Building	-	-	145 x 60
14	Unidentified area	-	-	145 x 60 (approx)
15	Building	-	-	70 x 35
16	Possible building	-	-	55 x 45
17	Possible building	-	-	70 x 35
18	Building	-	-	70 x 35
19	Possible building (L-shape)	-	-	70 x 35 (main) 40 x 35 (wing)
20	Building	-	Hip	65 x 65
21	Possible building	-	-	55 x 45
22	Building	-	-	55 x 40
23	Unidentified area	-	-	60 x 50
24	Unidentified area	-	-	100 x 90
25	Unidentified area	-	-	110 x 90

III. ANTENNAS

No antennas are visible on the [] aerial photography. Ground photography of 1957-58 shows four guyed stick masts which support

- 108 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

vertical cage dipoles, a guyed lattice tower supporting two microwave horns, and a self-supporting lattice tower probably for triangulation (Figures 69 and 70). All these items are in the northeastern part of the area.




FIG. 68. LINE DRAWING OF CHERNEVO RADIO STATION




FIG. 69. CHERNEVO RADIO STATION Near view showing four guyed stick masts (1953)

- 109 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 70. CHERNEVO RADIO STATION View of the buildings and a lattice tower supporting two microwave horns (1953)

25X1D

Ground Photography

25X1Q

MAP DATA:

ATMP

COLLATERAL REPORTS:

25X1D

25X1Q

COORDINATES: 55°50'N 37°17'E

25X1D

- 110 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

RADIO STATIONS IN MOSCOW, 1958



FIG. 71

- 111 -

TOP SECRET

TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 89

MOSCOW RADIO STATION

I. GENERAL

Moscow Radio Station (No. 89) is located approximately one nautical mile east of the Kremlin near the corner of Chkalova Ulitsa and Nikoloy-amsk Nab (Figure 72). The site can be identified on [REDACTED] aerial photography, but no towers or masts exist. Ground photography of 1956-57




FIG. 72. LOCATION MAP

shows that the area is fenced and contains three self-supporting steel towers reportedly 250 feet high and one guyed steel tower reportedly 75 feet high (Figure 74). Collateral reports indicate that this station may function as a radio station and/or as a jamming station.

II. STRUCTURES

Three buildings are located in close proximity to the four towers.

- 112 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

Two were in existence in [REDACTED] the third is visible on 1956 ground photography. All three buildings are large enough to accommodate the equipment necessary to operate the installation.




FIG. 73. MOSCOW RADIO STATION (NO. 89)

- 113 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59




FIG. 74. MOSCOW RADIO STATION (NO. 89) A southeast view showing all four steel towers (1956)

III. ANTENNAS

There are three self-supporting steel towers reportedly 250 feet high and one guyed steel tower reportedly 75 feet high located at this site (Figure 74). Two of the self-supporting towers are identical in appearance, and each contains an octagon-shaped platform approximately 30 feet in diameter at the top. Protruding approximately 15 feet beyond the outer limits of the platform are four steel arms constructed at right angles to each other (Figure 75). These arms are supported by a cable connected to a single vertical steel support which extends above the floor of the platform. In addition, each arm serves as the upper support for a 70-foot-long vertically hung cage antenna. Approximately 70 feet below the octagon platform is a second platform. This platform also has four arms extending out which anchor the terminating ends of the cage antennas hung from the top platform and which serve as the upper support for four additional

- 114 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59



FIG. 75. MOSCOW RADIO STATION (NO. 89) View of the octagon-shaped platform with four arms supporting vertically hung cage antennas (1956)




FIG. 76. MOSCOW RADIO STATION (NO. 89) View of a self-supporting steel tower showing vertically hung cage antennas (1957)

- 115 -

TOP SECRET [REDACTED]

TOP SECRET

PIC/JR-8/59

80-foot-long vertically hung cage antennas. Approximately 80 feet below the second platform is a third platform with four arms which are identical to those above and which anchor the terminating ends of the cage antennas hung from the second platform. Four feed lines extend up each leg of each of these two 250-foot towers, making a total of 16 feed lines which




FIG. 77. MOSCOW RADIO STATION (NO. 89) Example of cage antennas strung out from a 250 foot tower and probably anchored to the ground (1957)

serve the cage antennas on each tower. The third 250-foot-high self-supporting steel tower also has cage antennas mounted on it in a manner identical to that described above (Figures 75 and 76). Other cage antennas are supported by the 250-foot towers and are probably anchored to the ground (Figure 77). The fourth tower, a guyed steel tower, supports an undetermined number of horizontal cage antennas which are strung between this tower and the other three 250-foot towers (Figure 78).

- 116 -

TOP SECRET

TOP SECRET

PIC/JR-8/59





FIG. 78. MOSCOW RADIO STATION (NO. 89) View of the cage antennas strung between towers and also the feed lines which extend up each leg of the 250 foot towers (1956)

Ground photography shows two cage antennas constructed in series, and this may be done in other cases not discernible on the available photography. All the cage antennas observed on ground photography are center-fed.



- 117 -

TOP SECRET CHESSE
NOFORN

TOP SECRET

PIC/JR-8/59

Ground Photography

25X1C

MAP DATA:

ATMP

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°44'N/37°39'E

25X1D

- 118 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

NUMBER 94

MOSCOW TELEVISION STATION

I. GENERAL

Moscow Television Station is located 1.5 nautical miles south of the Kremlin on Sirotsky Per. between Shabolovka Ulitsa and Drovyanoy Pi. Pr. The station is reported to include several buildings and two self-supporting steellattice towers. The activities reported to be carried on at the station include television broadcasting and radio and television research (Figure 79).



FIG. 79. MOSCOW TELEVISION STATION

- 119 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 80. LINE DRAWING OF MOSCOW TELEVISION STATION

11. STRUCTURES

Aerial photography [] shows the station to be located in a densely built-up section of Moscow. Since it cannot be determined whether all or only some of the structures in the immediate vicinity are associated with the station, the following table lists all structures immediately surrounding the self-supporting steel tower present. [] A building reported to be under construction in [] contains 11 large television studios, the largest of which has approximately 1,000 square meters of floor space.

The following is a tabulation of structures in the area [] (item numbers are keyed to Figure 80).

- 120 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Unidentified	3	Hip	70 x 65
2	Unidentified	1	Hip	75 x 35
3	Unidentified	3	Valley	-
3a	Base	3	Valley	160 x 60
3b	Wing	3	Valley	50 x 50
4	Unidentified	1	-	25 x 30
5	Possible cooling pond	-	-	25 dia.
6	Unidentified	-	-	70 x 35
7	Possible transmitter building	2 & 3	Complex	-
7a	Wing	2	-	170 x 50
7b	Base	2	-	50 x 45
7c	Wing	2 & 3	-	170 x 65
8	Support-type building	1	Gable	175 x 55
9	Unidentified	3	-	-
9a	Base	3	-	85 x 45
9b	Wing	3	-	50 x 45
10	Unidentified	1	Gable	50 x 35
11	Unidentified	3	Valley	-
11a	Base	3	Valley	80 x 45
11b	Wing	3	Valley	70 x 50
11c	Wing	3	Valley	70 x 50
12	Unidentified	1	-	110 x 45

111. ANTENNAS

One self-supporting conical steel tower 440 feet high is visible on [] photography. A television antenna array, identified on 1956 ground photography, is mounted at the top of this tower (Figure 81a). Other antennas mounted on this tower include vertically hung cage dipoles, horizontal dipoles, and probable microwave dishes. A catwalk extends from the base

- 121 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

of the tower to the transmitter building. Another self-supporting steel lattice tower reported to be approximately 400 feet high is identified on 1956 ground photography. This tower also has a television antenna array mounted on the top (Figure 81b).




FIG. 81. MOSCOW TELEVISION STATION

a. View of self-supporting conical steel tower with television antenna array mounted on top. (1956)

b. View of self-supporting lattice tower with television antenna array mounted on top. (1956)

25X1D

Ground Photography

25X1C

- 122 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

MAP DATA:

ATMP []

25X1D

COLLATERAL REPORTS:

25X1C

COORDINATES: 55°43'N/37°36'E

25X1D

- 123 -

TOP SECRET

25X1

TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 98

MOSCOW RADIO STATION

A radio station is located in the science building at Moscow State University. The science building is 3.5 nautical miles southwest of the Kremlin and just north of the junction of Lomonosovskiy Prospekt and Lebedeva Ulitsa. Ground photography of 1958 shows several antennas mounted on the roof of the science building. The antennas which can be seen are two yagi arrays, one of which is a seven-element rotating yagi; vertically hung dipoles and horizontal cage antennas supported by a sectional lattice mast; and one unidentified antenna on top of this mast (Figure 83). The science building is visible on 1956 aerial photography, but the scale of the photography precludes identification of any antennas on the roof.




FIG. 82. MOSCOW RADIO STATION (NO. 98)

- 124 -


TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59



FIG. 83. MOSCOW RADIO STATION (NO. 98) Antenna arrays on top of the Moscow State University Science Building (1957).



MAP DATA:
Town Plan Moscow 1:35,000

COLLATERAL REPORTS:

COORDINATES: 55°42'N/37°32'E

25X1D

- 125 -

TOP SECRET [REDACTED]


TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 103

MOSCOW RADIO STATION

A radio station is located at the Post and Telegraph Building in Moscow. The building is 0.3 nautical miles northwest of the Kremlin at Gorkogo Ulitsa No. 7. The Ministry of Communications is also reported to be located here. Aerial photography [REDACTED] shows that the build-




TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

ing is a four-story quadrangle-type structure with a valley-type roof. The dimensions of the four sides are 410 by 90 feet, 125 by 90 feet, 400 by 90 feet, and 110 by 90 feet. The main entrance of the building is at the northernmost corner. This building is five stories high, is oval-shaped, and has a flat roof. Ground photography of 1957 shows four stick masts, two probable VHF antennas, and two unidentified antennas on top of the flat-roof part of the building. One of the unidentified antennas is reported to be a maypole type and the other to be a UHF antenna. Approximately four stick masts are located on other sections of the roof. Poor resolution of aerial photography [REDACTED] prevents identification of the building.



MAP DATA:
ATMP

COLLATERAL REPORT:

COORDINATES: 55°45'N/37°36'E

25X1D

- 127 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC JR-8/59

NUMBER 104

MOSCOW RADIO STATION

A radio station with a palm-tree-type tower is reported to be located 3 nautical miles west of the Kremlin. This tower cannot be identified on [REDACTED] aerial photography. The accompanying 1955 ground photography shows the tower, a self-supporting steel structure over 100 feet high with four sails extending up and out from the top of the tower and constructed at approximately 60° to the horizontal. Attached to the top of the tower are possibly four wires which support diagonally strung cage dipoles. These dipoles are anchored to the ground at an undetermined distance from the base of the tower. In addition, a vertically hung cage dipole extends down one side of the tower and is probably anchored at the base. Although vertically hung cage dipoles cannot be seen mounted on all sides of this tower, their existence is possible. This tower is similar to the towers at Moscow Radio Station (No. 89). The palm-tree tower is reported to have a radio-jamming function.



FIG. 85. MOSCOW RADIO STATION (NO. 104) Showing palm-tree-type tower, (1955)

- 128 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

MAP DATA:
ATMP [REDACTED]

COLLATERAL REPORTS:
[REDACTED]

COORDINATES: 55°44'N/37°32'E
[REDACTED]

25X1C

25X1C

- 129 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 107

OKTYABR'SKIY ANTENNA FARM

I. GENERAL

Oktyabr'skiy Antenna Farm is located in the northwestern sector of Moscow, 5 nautical miles (nm) west-northwest of the Kremlin and 1 1/2 nm west of Moscow Central Airfield (Figure 86). This antenna farm, which is reported to be the oldest radio transmitting station in the USSR,




FIG. 86. LOCATION MAP

is road- and rail-served, fenced, and covers approximately 240 acres. No service utilities are visible on the photography, but a power plant is reported to be under construction adjacent to the eastern fence, and several water wells are reported to be located on the farm property.

Aerial photography [REDACTED] shows two transmitter buildings with adjacent cooling ponds, numerous support structures, and an antenna

- 130 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59




FIG. 87. OKTYABR'SKIY ANTENNA FARM

- 131 -

TOP SECRET [REDACTED]

TOP SECRET

PIC/JR-8/59




FIG. 88. LINE DRAWING OF OKTYABR'SKIY ANTENNA FARM

25X1 farm containing at least 60 stick masts supporting numerous types of antenna arrays (Figures 87 and 88).

Ground photography of 1957 and collateral reports of 1946-51 indicate that several hundred antenna arrays are located at this farm. These arrays include caged dipoles, horizontal dipoles, vertical radiators, and rhombics. Although this installation is covered by [] aerial photography, the resolution is too poor for detailed interpretation.

III. STRUCTURES

The following is a tabulation of the structures within the area as of [] (item numbers are keyed to Figure 88).

- 132 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

Item No.	Identification	Stories	Roof Type	Dimensions (feet)
1	Transmitter building	4	Complex	195 x 70
2	Support building	1	Gable	75 x 20
3	Support building	1	Gable	55 x 25 (main) 25 x 25 (wing)
4	Support building	1	Gable	50 x 25
5	Underground shelter U/C	-	-	530 x 175
6	Cooling pond	-	-	45 dia.
7	Structure U/C	-	-	Undefinable
8	Structure U/C	-	-	35 dia.
9	Structure U/C	-	-	Undefinable
10	Structure U/C	1	-	170 x 10
11	Support building	1	Gable	40 x 30
12	Cooling pond	-	-	45 dia.
13	Transmitter building	-	-	195 x 70 (approx)
14	Support building	1	Gable	50 x 25
15	Standpipe	-	-	30 dia. 70 high (approx)
16	Support building	3	Flat	80 x 80 (over-all)
17	Possible storage tank	-	-	20 dia.
18	Support building	1	Shed	15 x 15
19	Support building	1	Gable	50 x 30
20	Support building	2	-	90 x 60
21	Support building	2	Gable	80 x 30
22	Support building	1	Gable	60 x 25
23	Support building	1	Gable	55 x 30
24	Support building	1	Gable	65 x 35
25	Possible tuning shack	1	-	15 x 15
26	Possible tuning shack	1	-	15 x 15
27	Possible tuning shack	1	-	15 x 15
28	Possible tuning shack	1	-	15 x 15

- 133 -

TOP SECRET CHESSE
NOFORN

TOP SECRET

PIC/JR-8/59



FIG. 89. OKTYABR'SKIY ANTENNA FARM View of approx. 35 guyed stick masts (1957)

III. ANTENNAS

25X1 A total of 60 stick masts visible on [] aerial photography are plotted on a layout diagram (Figure 88). No antenna patterns can be identified on this photography, but portions of feed lines are visible and are plotted. The guy-wire anchor footings under construction in the western part of the installation indicate that lattice masts could be installed later. These masts would be approximately 875 feet apart. The anchor footings are approximately 140 and 310 feet, respectively, out from the projected mast base locations. Post-World War II reports state that there are several hundred stick masts of varying heights located within the area. Antennas visible on 1957 ground photography are horizontal caged dipoles, one of which consists of six wires, and numerous stick masts in possible rhombic patterns (Figures 89, 90, and 91). There are at least six ladder-type supports with two crossarms each located within the area. Horizontal wires strung between these supports cannot be identified on 1957 ground photography; however, these supports are of the type normally used to support high-frequency curtain arrays consisting of a radiator and a reflector.

- 134 -

TOP SECRET

TOP SECRET

PIC/JR-8/59




FIG. 90. OKTYABR'SKIY ANTENNA FARM View of three tall towers, two guyed steel towers, and numerous guyed masts.




FIG. 91. OKTYABR'SKIY ANTENNA FARM Near view of guyed masts and a horizontal cage antenna (1957).

- 135 -

TOP SECRET

TOP SECRET

X1
X1

TOP SECRET [REDACTED]

PIC/JR-8/59

X1

25X1D

25X1C

MAP DATA:
ATMP [REDACTED]

25X1D

COLLATERAL REPORTS:

25X1C

- 136 -

TOP SECRET [REDACTED]

X1
X1X1
X1

TOP SECRET [REDACTED]

PIC/JR-8/59

NUMBER 108

MOSCOW RADIO STATION

A radio station is reported to be located at Petrovskiy Palace. The palace is 3.3 nautical miles northwest of the Kremlin, immediately northeast of Moscow Central Airfield, and 1,750 feet northwest of Dynamo Stadium. The station covers approximately 9 acres and consists of a large dome-roofed building 160 by 160 by 60 feet. The building is enclosed on three sides by curving wall-like structures 50 feet wide and 40 feet high. The wall is interrupted by eight towers. Aerial photography of [REDACTED] reveals no evidence of a radio station or antennas at the palace but ground photography of 1955 shows two stick masts, reportedly antennas, protruding from two towers on the palace wall (Figure 92).



FIG. 92. MOSCOW RADIO STATION (NO. 108). View of Petrovskiy Palace with two stick masts mounted on top of old fortifications, 1955.

- 138 -

TOP SECRET [REDACTED]

X1
X1

TOP SECRET [REDACTED]

PIC/JR-8/59

25X1C

COORDINATES: 55°47'N/37°29'E

25X1D

TOP SECRET [REDACTED]

25X1
25X125X1
25X1

TOP SECRET [REDACTED]

PIC/JR-8/59




FIG. 93. MOSCOW RADIO STATION (NO. 108). [REDACTED]

Collateral information [REDACTED] indicates that the palace was then the headquarters for long-range aviation (bomber) communications and the control center for up to ten direction-finding and navigation aid stations in the Moscow area. One station was reported on the palace grounds but was moved before the end of World War II.

- 139 -

TOP SECRET [REDACTED]

25X1 25X1

25X1
25X1

TOP SECRET

PIC/JR-8/59

25X1D

Ground Photography

25X1D

MAP DATA:

ATMP
Town Plan Moscow 1:35,000

25X1C

COLLATERAL REPORT:

25X1C

COORDINATES: 55°47'N/37°33'E

25X1D

TOP SECRET

TOP SECRET

PIC/JR-8/59

There is tabulated in the table beginning on the following page all data available on the remaining 81 installations.

TOP SECRET

TOP SECRET

PIC/JR-8/59

RADIO STATIONS WITHIN A 50-

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
1	Possible radio station, 58 nm N of Moscow near Taldom	56°43'N/37°34'E	Reported to contain stick masts arranged in two large semi-circles with large steel towers at their geometric centers. Cannot be identified on photography.
2	Radio station, 56 nm N of Moscow and about 6 nm NW of village of Verbulki	56°35'N/37°29'E	Reported to contain a group of towers approx. 150-250' high aligned approx. NE/SW. Cannot be identified on photography.
3	Possible radio station, 45.5 nm NE of Moscow and 2 nm N of Zagorsk	56°20'N/38°08'E	Reported to contain two masts 60' high and 200' apart; no connecting wires observed. Cannot be identified on photography.
4	Antenna farm, 31 nm N of Moscow near Repikhovo	56°13'N/37°59'E	Reported to contain approx. 50 stick masts, 40' high, arranged in two groups. Cannot be identified on photography.
5	Radio station, 24.5 nm NE of Moscow and 1.5 nm W of Moscow canal, and 4 km S of Iksha Lock	56°09'N/37°20'E	Reported to contain 30 masts and a 300' tower.
6	Radio station, 32 nm NE of Moscow and just E of Moscow/Lagorsk highway between 43 and 45 km markers	56°05'N/37°07'E	See detailed analysis.

TOP SECRET

TOP SECRET

PIC/JR-8/59

NAUTICAL-MILE RADIUS OF MOSCOW.

COLLATERAL REFERENCES	MAP REFERENCES	PHOTO COVERAGE	COVERAGE
			None
			None
			None
			None
			None

25X1C

25X1D

TOP SECRET

25X1
25X1

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
1	Passive radio station, 4000 nm E of Moscow near Orekhovo-Zuevo at 19 km mark	55°47'N/37°05'E 25X1D	Reported to contain three triangular-shaped 500' masts, probably guyed steel lattice towers. Cannot be identified on [] photography.
2	Radio station, 27 nm E of Moscow and 3 nm S of Noginsk	55°50'N/37°22'E 25X1D	See detailed analysis.
9	Radio station, 27 nm E of Moscow and 3 nm S of Noginsk	55°50'N/37°22'E 25X1D	See detailed analysis.
10	Radio station, 17.5 nm NE of Moscow and 3 nm SE of Shchelkovo	55°52'N/37°04'E 25X1D	See detailed analysis.
11	Radio station, 16 nm NE of Moscow at Shchelkovo	55°51'N/37°00'E 25X1D	Cannot be identified on [] photography.
12	Radio station, 13 nm NE of Moscow and 1.5 nm E of Kaliningrad	55°55'N/37°52'E 25X1D	Reported to be under construction. Cannot be identified on [] photography.
13	Radio station, 14.5 nm NNE of Moscow and 400 yards E of electrified railroad in village of Tarasovka	55°56'N/37°49'E 25X1D	Reported to contain 20 stick masts 30' to 60' high supporting squirrel-cage-type antennas. Site has been located on [] photography, but quality of photography precludes positive identification as a radio station.


- 144 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO COVERAGE



25X1C

TOP SECRET

25X1D

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
14	Radio station, 11.5 nm NE of Moscow on grounds of Moscow Military Communications Institute	55°56'N/37°44'E 25X1D	See detailed analysis.
15	Radio station, 12 nm N of Moscow and 1 nm SE of Belyaninovo	55°56'N/37°40'E 25X1D	See detailed analysis.
16	Radio station, 13 nm N of Moscow near Afanasovo	55°57'N/37°39'E 25X1D	Cannot be identified on [] photography.
17	Probable radio station, 11.5 nm N of Moscow at Dolgoprudnaya	55°56'N/37°31'E 25X1D	Reported to contain a small number of stick masts within a factory area. Cannot be identified on [] photography.
18	Krug site, 10 nm NE of Moscow and just SS V of Mytishchi	55°54'N/37°42'E 25X1D	Reported Wullenweber array. Cannot be identified on [] photography. Possibly same as 19.
19	Radio station, 10 nm NE of Moscow and just E of Moscow/Mytishchi Airfield	55°54'N/37°42'E 25X1D	Reported to contain 36 wooden masts. Cannot be identified on [] photography. Possibly same as 18.


- 146 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO COVERAGE



TOP SECRET

25X1D
25X1D

X1

TOP SECRET [REDACTED]

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
20	Radio station, 8.5 nm N of Moscow and just S of village of Chelobut'yev.	55°53'N/37°41'E 25X1D	Reported to contain 20 masts 45' high in rows of 5, each with 2 squirrel-cage-type antennas, and 4 masts 60' high, 10' apart, with 5' by 10' wire mesh between. Cannot be identified on [REDACTED] photography.
21	Radio station, 7.5 nm N of Moscow and S of Yaroslavl Shosse (highway) in Babushkin	55°51'N/37°42'E 25X1D	Cannot be identified on [REDACTED] photography. Ground photography of 1956 shows approx. 16 stick masts and one guyed steel lattice mast with microwave parabola on top. (See ground photo, Figure 94.)
22	Radio station, 7 nm NE of Moscow and just N of Izmaylovo Airfield	55°48'N/37°47'E 25X1D	Ground photography of 1956 shows a control building and 8 stick masts (See ground photo, Figure 95.) Cannot be identified on [REDACTED] photography.
23	Radio station, 8 nm NE of Moscow and just NE of Izmaylovo Airfield	55°48'N/37°48'E 25X1D	Reported to be a probable transmitting station with 30 wooden masts strung with horizontal HF half-wave cage antennas; one mast mounts 4 Bed Rests. (See ground photo, Figure 96.) Cannot be identified on [REDACTED] photography.

X1
X1

X1

X1

X1

- 148 -

TOP SECRET [REDACTED]

X1

TOP SECRET [REDACTED]

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
24	Radio station, 9.5 nm E of Moscow and just S of Entuziastov Shosse	55°47'N/37°53'E 25X1D	Reported to contain stickmasts approx. 60-80' high with 6 squirrel-cage-type antennas in a "V" pattern. Cannot be identified on [REDACTED] photography.
25	Radio station, 11 nm E of Moscow in town of Leonovo	55°47'N/37°56'E 25X1D	Reported to contain 5 masts 40' high supporting center-fed squirrel-cage-type antennas. Cannot be identified on [REDACTED] photography.
26	Radio station, 11.5 nm E of Moscow and S of Entuziastov Shosse	55°47'N/37°57'E 25X1D	Reported to contain 12 masts forming a combination of squirrel-cage and rhombic antennas. Cannot be identified on [REDACTED] photography.
27	Radio station, 14 nm E of Moscow in vicinity of Novaya and just N of Entuziastov Shosse	55°48'N/38°00'E 25X1D	Reported to contain approx. 30 masts 60' high making up squirrel-cage and rhombic antennas. Cannot be identified on [REDACTED] photography.
28	Radio station, 14 nm E of Moscow in vicinity of Novaya and just N of Entuziastov Shosse	55°48'N/38°01'E 25X1D	Reported to contain 30 masts. Cannot be identified on [REDACTED] photography.

X1

X1

X1

X1

X1

X1


- 150 -

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO COVERAGE [REDACTED] COVER PAGE



25X1C

TOP SECRET [REDACTED]

25X1
25X1


25X1

25X1
25X1

TOP SECRET [REDACTED]

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO COVERAGE [REDACTED] COVER PAGE



25X1D

25X1C

TOP SECRET [REDACTED]

25X1
25X1

25X1

25X1
25X1

SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
29	Radio station, 14 nm. E of Moscow and S of Moscow/Gorkiy rail line in vicinity of 27 km mark	55°45'N/38°03'E [redacted] 25X1D	Reported to contain 12 masts 80' high with double feeder from center of suspended wires. Cannot be identified on [redacted] photography.
30	Antenna farm, 12 nm E of Moscow and just S of Moscow/Gorkiy rail line near Kupavna	55°45'N/38°06'E [redacted] 25X1D	See detailed analysis.
31	Radio station, 26 nm E of Moscow, 4.75 nm S of Noginsk, and 1.3 nm W of Elektrostal	55°46'N/38°25'E [redacted] 25X1D	See detailed analysis.
32	Antenna farm, 9 nm E of Moscow and S of road in Malyye Krutitsy	55°42'N/37°05'E [redacted] 25X1D	Reported to contain 50-60 poles 60-70' high making up a combination of squirrel-cage and rhombic antennae. Cannot be identified on [redacted] photography.
33	Antenna farm, 11.5 nm SE of Moscow between Panki and Tomilino	55°39'N/37°55'E [redacted] 25X1D	Reported to contain fishbone antenna about 200 meters long, several rhombics, and numerous horizontal dipoles. Cannot be identified on [redacted] photography.

- 152 -

- 132 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
34	Radio station, 7.5 nm SW of Moscow and just E of Kon'kovo	55°38'N/37°32'E [REDACTED] 25X1D	Cannot be identified on [REDACTED] photography.
35	Radio station, 17 nm ESE of Moscow and immediately W of Bykovo Airfield	55°37'N/38°05'E [REDACTED] 25X1D	See detailed analysis.
36	Radio station, 9 nm S of Moscow and just NE of Biryulevo	55°36'N/37°41'E [REDACTED] 25X1D	Reported to contain six masts 40' high forming three squirrel-cage-type antennas centered fed by two wire transmission lines, separated by spreaders. Cannot be identified on [REDACTED] photography.
37	Antenna farm, 10 nm S of Moscow in vicinity of Biryulevo	55°36'N/37°41'E [REDACTED] 25X1D	See detailed analysis.
38	Radio station, 10 nm S of Moscow at Biryulevo	55°35'N/37°40'E [REDACTED] 25X1D	Cannot be identified on [REDACTED] photography. Possibly the same as No. 37.
39	Possible radio station, 12.5 nm S of Moscow at Rastorguyev	55°33'N/37°40'E [REDACTED] 25X1D	Reported radio station at Rastorguyev. Cannot be identified on [REDACTED] photography.
40	Antenna farm, 17 nm S of Moscow and on northern outskirts of Domodedovo	55°25'N/37°45'E [REDACTED] 25X1D	See detailed analysis.

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES	MAP REFERENCES	PHOTO COVERAGE	
		<div data-bbox="1261 606 1421 640" style="border: 1px solid black; height: 60px; margin-bottom: 10px;"></div> <div data-bbox="1261 640 1421 674" style="border: 1px solid black; height: 60px; margin-bottom: 10px;"></div> <div data-bbox="1261 674 1421 705" style="border: 1px solid black; height: 60px; margin-bottom: 10px;"></div> <div data-bbox="1261 705 1421 739" style="border: 1px solid black; height: 60px; margin-bottom: 10px;"></div> <div data-bbox="1261 739 1421 772" style="border: 1px solid black; height: 60px; margin-bottom: 10px;"></div> <div data-bbox="1261 772 1421 802" style="border: 1px solid black; height: 54px;"></div>	

25X1C

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES	MAP REFERENCES	PHOTO COVERAGE	

25X1

- 155 -

TOP SECRET

25X

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
41	Radio station, 50.5 nm S of Moscow at Serpukhov	54°54'N/37°24'E 25X1D	Reported to contain an antenna 30' high located on the roof of a fire station. Cannot be identified on [] photography.
42	Radio station, 48.5 nm S of Moscow at km 94 from Moscow on Moscow/Serpukhov road	54°57'N/37°25'E 25X1D	Reported to contain one Nadenenko-type dipole stretched between two 60' masts, four masts 40' high, and one building. (See ground photo, Figure 97.) Cannot be identified on [] photography.
43	Radio station, 37.5 nm S of Moscow at Chekhov	55°09'N/37°27'E 25X1D	Reported to contain a ground plane antenna approx. 30' high on the roof of a fire station. Cannot be identified on [] photography.
44	Radio station, 23 nm S of Moscow and 500 yards W of Moscow/Tula highway	55°22'N/37°31'E 25X1D	Reported to contain 30-40 steel towers approx. 100-200' high with connecting wires.
45	Krug site, 22.5 nm S of Moscow, 4 nm SW of Podolsk, and 1 nm SE of village of Ozno-bishino	55°23'N/37°28'E 25X1D	Reported to contain about 50 short masts equally spaced around the circumference of a circle; at the center is a small square hut.

- 156 -
TOP SECRET []

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES	MAP REFERENCES	PHOTO COVERAGE	COVERAGE

25X1C - 157 -
TOP SECRET []

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
46	Antenna farm, 13 nm S of Moscow and adjacent to SW corner of Butovo	55°32'N/37°33'E 25X1D	See detailed analysis.
47	Krug site, 19.5 nm SSW of Moscow near village of Vlas'yev	55°28'N/37°22'E 25X1D	Reported Wullenweber array. The site cannot be identified on [] photography.
48	Radio station, 19.5 nm SW of Moscow and midway between Vatatutinki and Krasnaya Pakhra	55°28'N/37°18'E 25X1D	Reported to contain four poles 30-40' high making up one squirrel-cage antenna and one 60' mast with possible Bed Rest antenna. (See ground photo, Figure 98.) Cannot be identified on [] photography.
49	Radio station, 18 nm SW of Moscow along the east side of Moscow/Kaluga highway between towns of Desna and Vatatutinki	55°29'N/37°20'E 25X1D	See detailed analysis.
50	Radio station, 17.5 nm SW of Moscow along east side of Moscow/Kaluga highway between towns of Desna and Vatatutinki	55°30'N/37°21'E 25X1D	See detailed analysis.
51	Radio station, 18 nm SW of Moscow near Vatatutinki	55°30'N/37°19'E 25X1D	Reported to contain approx 20 tall poles. Cannot be identified on [] photography.

- 158 -
TOP SECRET []

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES	MAP REFERENCES	PHOTO REFERENCES	COVERAGE

25X1C 25X1D

- 159 -
TOP SECRET []

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
52	Antenna farm, 17.5 nm SW of Moscow, 2.5 km S of Desna, and behind a military area W of Moscow/Kaluga road	55°30'N/37°21'E 25X1D	Reported small antenna farm and one 25' pole with a dish facing SE. Cannot be identified on [] photography.
53	Radio station, 17.5 nm SW of Moscow along east side of Moscow/Kaluga highway between towns of Desna and Vnutinki	55°30'N/37°22'E 25X1D	See detailed analysis.
54	Radio station, 17 nm SW of Moscow along east side of Moscow/Kaluga highway between towns of Desna and Vnutinki	55°30'N/37°23'E 25X1D	See detailed analysis.
55	Antenna farm, 15.5 nm SSW of Moscow and approximately 1 nm S of village of Voskresenskoye	55°31'N/37°26'E 25X1D	Reported antenna farm adjacent to a military barracks area. (See ground photo, Figure 99.) Cannot be identified on aerial photography. []
56	Antenna farm, 15 nm SW of Moscow near Penino	55°32'N/37°23'E 25X1D	Reported to contain 100 masts and to contain a combination of rhombic and squirrel-cage antennas. Cannot be identified on [] photography.


- 160 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO REFERENCES COVERAGE

25X1C
TOP SECRET

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
57	Antenna farm, 12 nm SSW of Moscow and 3 nm WNW of Butovo	55°34'N/37°28'E 25X1D	See detailed analysis.
58	Antenna farm, 8.5 nm SSE of Moscow at the 19 km mark and on E side of Moscow/Kaluga highway	55°37'N/37°31'E 25X1D	See detailed analysis.
59	Antenna farm, 6.5 nm SW of Moscow between Moscow/Kaluga and Moscow/Kiev highways and less than 1 nm W of Vorontsovo	55°39'N/37°31'E 25X1D	See detailed analysis.
60	Radio station, 10 nm SW of Moscow at Rummyantsevo	55°37'N/37°25'E 25X1D	Cannot be identified on [] photography.
61	Radio station, 12 nm SW of Moscow and 1 nm N of Peredel'tsy	55°36'N/37°21'E 25X1D	Reported to contain one squirrel-cage antenna and 2 poles 50' high, spaced approx. 100-150' apart. Possible communications system for Vnukovo A/F. (See ground photo, Figure 100.) Cannot be identified on [] photography.
62	Antenna farm, 16 nm VSW of Moscow and 2.5 nm WNW of Vnukovo Airfield	55°36'N/37°13'E 25X1D	See detailed analysis.

- 162 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO REFERENCES COVERAGE



25X1C

25X1D

TOP SECRET

25X1
25X1

25X1

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
72	Antenna farm, 11.5 nm NW of Moscow and 2 nm W of Khumka	55°53'N/37°23'E 25X1D	Reported to contain over 53 masts 90' high. Cannot be identified on [] photography. Possibly the same as No. 70.
73	Radio station, 19.5 nm NW of Moscow near Kryukovo and 1/2 nm S of Lenin-grad-Moscow rail line.	55°55'N/37°11'E 25X1D	Reported to contain 30-35 irregularly spaced masts, 60-75' high. Cannot be identified on [] photography.
74	Antenna farm, 26 nm NW of Moscow on W side of Moscow/Klin road	56°05'N/37°06'E 25X1D	Reported to contain 50-100 masts 50' high. Approx 4 km away are two masts approx. 300' high. Area contains administration and barracks-type buildings. Cannot be identified on [] photography.

TOP SECRET

PIC/JR-8/59


NO.	TYPE AND LOCATION	COORDINATES	REMARKS
75	Radio station, 35 nm NW of Moscow at Solnechnogorsk	56°11'N/36°58'E 25X1D	Reported to contain a VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
76	Radio station, 46 nm NW of Moscow at Klin	56°20'N/36°42'E 25X1D	Reported to contain one VHF antenna on top of fire station. Cannot be identified on [] photography.
77	Possible radio station, 46.5 nm NW of Moscow and 1/4 nm NE of center of Klin	56°20'N/36°43'E 25X1D	Reported to contain two steel towers, 100-200' high, with unidentified aerials on top. (See ground photo, Figure 102.) Cannot be identified on [] photography.
78	Radio station, 5.3 nm NNW of the Kremlin on Listrennichnaya Alleya	55°50'N/37°33'E 25X1D	Reported broadcasting station cannot be identified on [] photography.
79	Radio station, 4 nm N of the Kremlin and just E of Dmitrovskoye Shosse	55°45'N/37°35'E 25X1D	Reported radio station cannot be identified on [] photography.
80	Radio station, 4 nm NNE of the Kremlin in Sokolnicheskoy Park	55°45'N/37°40'E 25X1D	ILLEGIB

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO REFERENCES COVERAGE



TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO REFERENCES COVERAGE



25X1C

25X1D

TOP SECRET

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
81	Radio station, 4.5 nm NNE of the Kremlin on Bolshaya Olenia Ulitsa	55°45'N/37°41'E 25X1D	Reported military radio station cannot be identified on [] photography.
82	Radio station, 3.3 nm NE of the Kremlin and opposite the entrance to Sokolnichesky Park	55°47'N/37°40'E 25X1D	Reported to contain one VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
83	Radio station, 5 nm NE of the Kremlin and just N of Izmaylovskoye Shosse	55°47'N/37°45'E 25X1D	Reported radio station has been located on [] photography, but quality of photography precludes positive identification.
84	Radio station, 1.5 nm NE of the Kremlin at Sadovskaya Spasskaya	55°46'N/37°45'E 25X1D	Reported to contain a VHF antenna located on top of building housing the Ministry of Transport Machine Building. Three probable VHF antennas are visible on ground photography and the building can be identified on [] photography. (See ground photo, Figure 103.)
85	Radio station, 1.5 nm NE of the Kremlin at corner of Novaya Basmanaya and Sadovaya Chernogr	55°46'N/37°39'E 25X1D	Reported to contain 2 probable VHF antennas on top of Ministry of Railways Building. Building can be identified on [] photography.
86	Radio station, 1.5 nm NE of the Kremlin in block between Khari-ton Malaya Ulitsa and Kozlovsk B	55°46'N/37°39'E 25X1D	Reported to contain one radio antenna located on the Naval Komandatura building. Cannot be identified on [] photography.


- 172 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO REFERENCES COVERAGE



25X1G

TOP SECRET

TOP SECRET

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
87	Radio station, 2 nm NE of the Kremlin at Kasakova Ulitsa No. 20	55°45'N/37°40'E 25X1D	Reported to be an experimental radio station. Site has been located on [] photography, but quality of photography precludes positive identification as a radio station.
88	Radio station, 3.5 nm E of the Kremlin at Entuziastov Shosse No. 109	55°45'N/37°43'E 25X1D	Reported to contain one VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
89	Radio station, 1 nm E of the Kremlin near corner of Okhmalova Ulitsa and Nikoloyamsk Nab	55°44'N/37°39'E 25X1D	See detailed analysis.
90	Radio station, 0.6 nm SE of the Kremlin at Osipenko Ulitsa No. 37	55°44'N/37°38'E 25X1D	Reported to contain one VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
91	Radio station, 1.5 nm SE of the Kremlin at corner of Kamenshiki Bolshaya Ulitsa and Kamenshiki Malaya Ulitsa	55°44'N/37°39'E 25X1D	Reported to contain a VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
92	Radio station, 1 nm S of the Kremlin on Bolshe Spassobolranovsky Per.	55°44'N/37°37'E 25X1D	Reported broadcasting station cannot be identified on [] photography.


- 174 -

TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO COVERAGE COVERAGE



25X1C

TOP SECRET

TOP SECRET

PIC/JR-8/59


NO.	TYPE AND LOCATION	COORDINATES	REMARKS
93	Radio station, 1.7 nm S of the Kremlin on a street parallel with the lower part of Vostochnaya Ulitsa	55°42'N/37°39'E 25X1D	Reported to contain one VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
94	Television station, 1.5 nm S of the Kremlin at corner of Drovyanov Pl. and Sirotskiy P.	55°43'N/37°36'E 25X1D	See detailed analysis.
95	Radio station, 2 nm S of the Kremlin at Donskaya Ulitsa No. 60	55°43'N/37°36'E 25X1D	Reported to contain a VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
96	Radio station, 1.5 nm S of the Kremlin and just off Krymsky val Ulitsa	55°43'N/37°36'E 25X1D	Reported to contain a VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
97	Radio station, 2 nm SW of the Kremlin on Fuzenskaya Nab	55°43'N/37°35'E 25X1D	Reported probable VHF antenna on top of the Ministry of Defense building. Cannot be identified on [] photography.
98	Radio station, 3.5 nm SW of the Kremlin on grounds of Moscow State University	55°42'N/37°32'E 25X1D	See detailed analysis.
99	Probable radio station, 1.6 nm SW of the Kremlin near corner of Pirogovskaya Ulitsa and Devich. Polyak Pr.	55°44'N/37°34'E 25X1D	Reported radio tower cannot be identified on [] photography.

- 176 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO REFERENCES COVERAGE



25X1C

TOP SECRET

TOP SECRET

PIC/JR-8/59


NO.	TYPE AND LOCATION	COORDINATES	REMARKS
100	Radio station, 0.7 nm SW of the Kremlin on corner of Chisty Per and Ulitsa Kropotkinskaya	55°44'N/37°35'E 25X1D	Reported to contain 4 VHF antennas mounted on top of fire station. Cannot be identified on [] photography.
101	Radio station, 1.2 nm W of the Kremlin on Glasovskovo Ulitsa	55°45'N/37°35'E 25X1D	Reported broadcasting station. Cannot be identified on [] photography.
102	Radio station, 0.3 nm W of the Kremlin at Sobinovskiy Perevlok No. 6	55°45'N/37°36'E 25X1D	Reported to contain one VHF antenna mounted on top of fire station. Cannot be identified on [] photography.
103	Radio station, 0.3 nm NW of the Kremlin at Gorkogo Ulitsa No. 7	55°45'N/37°36'E 25X1D	See detailed analysis.
104	Radio station, reported to be located 3 nm W of the Kremlin	55°44'N/37°32'E 25X1D	See detailed analysis.
105	Radio station, 2.5 nm NW of the Kremlin near corner of Khroshevskeye Shosse and Begovaya Ulitsa	55°45'N/36°33'E 25X1D	Reported broadcasting station. Cannot be identified on [] photography.
106	Radio station, 3.5 nm WNW of the Kremlin and just S of Moscow Central Airfield	55°46'N/37°31'E 25X1D	Reported radio towers. Cannot be identified on [] photography.

- 178 -
TOP SECRET

TOP SECRET

PIC/JR-8/59

COLLATERAL REFERENCES MAP REFERENCES PHOTO COVERAGE COVERAGE



25X1C

TOP SECRET

TOP SECRET [REDACTED]

PIC/JR-8/59

NO.	TYPE AND LOCATION	COORDINATES	REMARKS
107	Antenna farm, 5 nm WNW of the Kremlin and 1.5 nm W of Moscow Central Air- field	55°47'N/37°29'E [REDACTED] 25X1D	See detailed analysis.
108	Radio station, 3.3 nm NW of the Kremlin and just NW of Dynamo Stadium	55°47'N/37°33'E [REDACTED] 25X1D	See detailed analysis.
109	Radio station, 4 nm NW of the Kremlin at Leningradskye Shosse No. 110	55°48'N/37°31'E [REDACTED] 25X1D	Reported to contain 2 VHF antennas mounted on top of fire station. Cannot be identified on [REDACTED] photography.

TOP SECRET [REDACTED]

PIC/JR-8/59

EGIB

EGIB

TOP SECRET [REDACTED]

TOP SECRET [REDACTED]

PIC/JR-8/59

COLLATERAL REFERENCES	MAP REFERENCES	PHOTO COVERAGE	COVERED
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]

25X1C

25X1D

TOP SECRET [REDACTED]

PIC/JR-8/59




FIG.96. RADIO STATION (NO. 23) View of radio station NE of Izmaylovo A. F. with 8 guyed stick masts, one mast with microwave horns mounted on top, and central building (1952).

FIG.97. RADIO STATION (NO. 42) View of radio station just north of Serapukha with five guyed stick masts and one central bldg. (1957).



TOP SECRET [REDACTED]

25X1
25X1

TOP SECRET

PIC/JR-8/59





FIG.98. RADIO STATION (NO. 48) View of radio station near Votuzinki with two guyed stick masts and a horizontal dipole antenna (1957).

FIG.99. ANTENNA FARM (NO. 55) View of one side of an antenna farm just south of Voskresenskoye with approx. 14 stick masts visible (1958).



- 184 -

TOP SECRET

TOP SECRET

PIC/JR-8/59



FIG.100. RADIO STATION (NO. 61) View of radio station north of ParadaPty with two guyed stick masts and control building (1951).



FIG.101. RADIO STATION (NO. 65) View of radio station on west side of Moscow with one guyed stick mast and control building (1956).

- 185 -

TOP SECRET

TOP SECRET

PIC/JR-8/59



FIG.102. POSSIBLE RADIO STATION (NO. 77) View of possible radio station 1/2 mile NE of Klin with two self-supporting steel towers (1956).




FIG.103. MOSCOW RADIO STATION (NO. 84) View of the building housing the Ministry of Transport Machine with three 2200' VLF antennas and one microwave parabolic mounted along the sides of the building (1955).

- 186 -

TOP SECRET

25X1
25X1

25X1
25X1

25X1



11